PROJECT DIRECTORY

PROJECT SITE: LAUDERDALE COUNTY AGRI-CENTER 1022 MS-19, MERIDIAN, MS 39301

PRIME PROFESSIONAL AND MECHANICAL ENGINEER: ENGINEERING RESOURCE GROUP 350 EDGEWOOD TERRACE DRIVE JACKSON, MS 39206 T: (601) 362-3552

F: (601) 366-6418

ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

REGULATORY STANDARDS

APPLICABLE CODES AND STANDARDS INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

2018- INTERNATIONAL BUILDING CODE 2018 - INTERNATIONAL MECHANICAL CODE

ASHRAE STANDARD 90.1-2010

PROJECT SUMMARY

PROJECT SCOPE OF WORK INCLUDES BUT IS NOT LIMITED TO THE FOLLOWING:

HUMAN SERVICES

BASE BID

- DEMOLITION OF CEILING
- DEMOLITION OF HVAC AND CONTROL SYSTEM INSTALLATION OF NEW HVAC AND CONTROL SYSTEMS
- INSTALLATION OF NEW CEILING, PATCHING AND PAINTING ELECTRICAL SYSTEMS DEMOLITION AND SERVICE TO NEW EQUIPMENT

EMERGENCY SERVICES / EMA

BASE BID

- DEMOLITION OF CEILING WHERE SHOWN
- DEMOLITION OF VAV UNITS AND CONTROL SYSTEM INSTALLATION OF NEW VAV UNITS AND CONTROL SYSTEM
- INSTALLATION OF NEW CEILING WHERE SHOWN, PATCHING AND PAINTING
- ELECTRICAL SYSTEMS DEMOLITION AND SERVICE TO NEW EQUIPMENT

AGRI-CENTER

ADD ALTERNATE #1

- DEMOLITION OF LOWER RESTROOM CEILING ٠
- INSTALLATION OF NEW HVAC SYSTEM
- INSTALLATION OF LOWER RESTROOM NEW CEILING, PATCHING AND PAINTING ELECTRICAL SYSTEMS DEMOLITION AND SERVICE TO NEW EQUIPMENT

SPECIAL PROJECT NOTES

1. ANY UTILITY OUTAGES SHALL BE COORDINATED WITH THE OWNER AND PROFESSIONAL AND SHALL BE PERFORMED DURING PERIODS CONVENIENT FOR THE OWNER. OUTAGES WILL LIKELY BE REQUIRED TO BE PERFORMED AT NIGHT, ON WEEKENDS, HOLIDAYS, ETC. (PERIODS OF LIGHT OR NO CAMPUS OCCUPANCY).

DWG. NO. DESCRIPTION

T0.1 TITLE SHEET

ARCHITECTURAL

- A1.1
- HUMAN SERVICES FIRST FLOOR CEILING PLAN HUMAN SERVICES - SECOND FLOOR CEILING PLAN A1.2 A1.3 EMERGENCY SERVICES / EMA - CEILING PLAN A1.4 AGRI-CENTER - LOWER RESTROOM CEILING PLAN - ADD ALT. #1

MECHANICAL

- M0.1 MECHANICAL LEGEND, ABBREVIATIONS, AND NOTES HUMAN SERVICES - FIRST FLOOR PLAN - HVAC DEMOLITION M1 1 M1 2 HUMAN SERVICES - SECOND FLOOR PLAN - HVAC DEMOLITION M1.3 HUMAN SERVICES - FIRST FLOOR PLAN - HVAC RENOVATION M1.4 HUMAN SERVICES - SECOND FLOOR PLAN - HVAC RENOVATION HUMAN SERVICES - FIRST FLOOR PLAN - HVAC VENTILATION AND PIPING M1.5 HUMAN SERVICES - SECOND FLOOR PLAN - HVAC VENTILATION AND PIPING M1.6 M1.7 HUMAN SERVICES - ENLARGED SCALE MECHANICAL ROOM PLAN - HVAC M1.8 HUMAN SERVICES - FIRST FLOOR PLAN - HVAC CONDENSATE RENOVATION HUMAN SERVICES - SECOND FLOOR PLAN - HVAC CONDENSATE RENOVATION M1.9 M1 10 HUMAN SERVICES - ENLARGED SCALE MECHANICAL ROOM PLAN - HVAC CONDENSATE M1.11 EMERGENCY SERVICES / EMA - FIRST AND SECOND FLOOR PLAN - HVAC DEMOLITION M1.12 EMERGENCY SERVICES / EMA - FIRST AND SECOND FLOOR PLAN - HVAC RENOVATION EMERGENCY SERVICES / EMA - ENLARGED SCALE MECHANICAL ROOM PLAN - HVAC M1.13 AGRI-CENTER - UPPER RESTROOM PLAN - HVAC M1 14 M1.15 AGRI-CENTER - LOWER RESTROOM PLAN - HVAC M5.1 MECHANICAL DETAILS M5.2 MECHANICAL DETAILS M5.3 MECHANICAL DETAILS M6 1 HUMAN SERVICES - MECHANICAL SCHEDULES M6.2 HUMAN SERVICES - MECHANICAL SCHEDULES EMERGENCY SERVICES / MECHANICAL SCHEDULES M6.3 AGRI-CENTER - MECHANICAL SCHEDULES - ADD ALTERNATE #1 M6.4 M7 1 HUMAN SERVICES - CONTROL SCHEMATICS
- M7.2 HUMAN SERVICES - CONTROL SCHEMATICS HUMAN SERVICES - CONTROL SCHEMATICS M7.3
- M7 4 EMERGENCY SERVICES - CONTROL SCHEMATICS
- M7.5 EMERGENCY SERVICES - CONTROL SCHEMATICS
- M7.6 EMERGENCY SERVICES - CONTROL SCHEMATICS EMERGENCY SERVICES - CONTROL SCHEMATICS M7.7
- M7.8 AGRI-CENTER - CONTROL SCHEMATICS

- VERIEY SAME WITH SHOP DRAWINGS.
- MUNICIPALITY, UTILITY COMPANY, OSHA, ETC.).
- WORK NOT DONE SO SHALL BE REMOVED AND REINSTALLED SATISFACTORILY.
- DRAWINGS, OR DIMENSIONS SUPPLIED TO THE CONTRACTOR.
- ALL CUTTING AND PATCHING SHALL MATCH ADJACENT SURFACES.
- TIME OF BID.
- DATE. TO ALLOW CLARIFICATION BY WRITTEN ADDENDUM.
- FUNCTIONAL, AND SAFE FACILITY, ANYTHING LESS SHALL BE UNACCEPTABLE.
- 12. ALL VIBRATING, OSCILLATING, NOISE PRODUCING OR ROTATING EQUIPMENT SHALL BE ISOLATED FROM ARCHITECT.
- ARCHITECT PRIOR TO INSTALLATION FOR CLARIFICATION.
- THE ARCHITECT AND CONSENT OF THE OTHER TRADE, IN WRITING.
- PURCHASER
- INSTALLERS, ETC.
- WHERE ACCESS IS COMPROMISED SHALL BE RELOCATED AT THE CONTRACTOR'S EXPENSE.
- FILLING PIPING SYSTEMS AS REQUIRED TO INSTALL THEIR NEW WORK.
- IMMEDIATELY BE REJECTED.
- WEIGHT IN THE DOWNWARD DIRECTION. ALL BRACING SHALL BE CONTRACTOR DESIGNED.

DRAWING INDEX

E3.2

ELECTRIC	CAL
E0.1	ELECTRICAL SYMBOLS LEGEND
E0.2	ELECTRICAL SCHEDULES & DETAILS
E1.1	HUMAN SERVICES BLDG ELECTRICAL 1ST FLOC
E1.2	HUMAN SERVICES BLDG ELECTRICAL 2ND FLOO
E1.3	HUMAN SERVICES BLDG ELECTRICAL SCHEDUL
E2.1	EMERGENCY SERVICES BLDG ELECTRICAL 1ST
E2.2	EMERGENCY SERVICES BLDG ELECTRICAL 2ND
E3.1	AGRI-CENTER BLDG ELECTRICAL UPPER LEVEL

GENERAL NOTES

EACH CONTRACTOR, SUPPLIER AND/OR MANUFACTURER SHALL REFER TO ALL DOCUMENTS PERTAINING TO THIS PROJECT AND COORDINATE ACCORDINGLY SO AS TO ENSURE ADEQUACY OF FIT. COMPLIANCE WITH SPECIFICATIONS, PROPER ELECTRICAL SERVICE, AND AVOID CONFLICT WITH ANY OTHER BUILDING SYSTEMS.

ALL OFFSETS, TURNS, FITTINGS, TRIM, DETAIL, ETC., MAY NOT BE INDICATED, BUT SHALL BE PROVIDED AS REQUIRED. ADDITIONAL ALLOWANCES SHALL BE INCLUDED FOR SAME AT EACH PROPOSERS' DISCRETION.

OBSERVE ALL APPLICABLE CODES, RULES AND REGULATIONS (CITY, COUNTY, LOCAL, STATE, FEDERAL

ALL SYSTEMS, EQUIPMENT, AND MATERIALS ARE TO BE INSTALLED IN A NEAT AN WORKMANLIKE MANNER.

WHERE MOUNTING HEIGHTS ARE NOT INDICATED OR ARE IN CONFLICT WITH ANY OTHER BUILDING SYSTEM. CONTACT THE ENGINEER BEFORE INSTALLATION. REFER ALSO TO ARCHITECTURAL WALL INTERIOR AND EXTERIOR WALL ELEVATIONS, CEILING HEIGHTS AND OTHER DETAILS OF THESE DOCUMENTS. REFERENCE SPECIFICATION 230010 "MECHANICAL GENERAL PROVISIONS" FOR COORDINATION DRAWING REQUIREMENTS.

DO NOT SCALE DRAWINGS, PRINTING DISTORTS SCALE. WORK SHALL BE LAID OUT FROM DIMENSIONED

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CUTTING AND PATCHING REQUIRED FOR THEIR WORK,

THESE DRAWINGS ARE ACCURATE TO THE BEST OF OUR KNOWLEDGE, HOWEVER LOCATIONS, DEPTHS, ELEVATIONS, AND SIZES WERE TAKEN FROM DIFFERENT SOURCES AND ARE SUBJECT TO DEVIATION. THE CONTRACTOR SHALL ASSUME SOME DEVIATIONS AND INCLUDE OFFSETS, ADDITIONAL PIPING, ETC. AT THE

ADVISE THE ENGINEER OF ANY CONFLICTS, ERRORS, OMISSIONS, ETC. AT LEAST TEN DAYS PRIOR TO BID

DEVIATION FROM SPECIFICATIONS OR PLANS REQUIRES PRIOR WRITTEN APPROVAL FROM THE ENGINEER AND MUST BE SUBMITTED IN WRITING NO LATER THAN TEN DAYS PRIOR TO THE BID DATE.

11. THE PURPOSE AND INTENT OF THE DOCUMENTS PERTAINING TO THIS PROJECT IS TO PROVIDE A COMPLETE,

SURROUNDING SYSTEMS IN AN APPROVED MANNER. NOISY, VIBRATING, OR STRUCTURALLY DAMAGING INSTALLATIONS SHALL BE SATISFACTORILY REPLACED OR REPAIRED AT THE INSTALLING CONTRACTOR'S EXPENSE. THE FINAL DECISION ON THE SUITABILITY OF A PARTICULAR INSTALLATION SHALL BE THAT OF THE

INSTALL EQUIPMENT, MATERIALS, ETC. IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND DIRECTIONS. IF IN CONFLICT WITH THE DESIGN INDICATED IN CONTRACT DOCUMENTS, ADVISE THE

14. ALL SUPPORTS FOR EQUIPMENT, DEVICES, OR FIXTURES SHALL BE UNIQUE FROM THE BUILDING STRUCTURE DO NOT SUPPORT FROM OTHER TRADES, EQUIPMENT OR SUPPORTS WITHOUT WRITTEN PERMISSION FROM

DEVIATIONS IN SIZE, CAPACITIES, FIT, FINISH, ETC. FOR EQUIPMENT FROM THAT SPECIFIED SHALL BE THE RESPONSIBILITY OF THE PURCHASER OF THAT EQUIPMENT. ANY PROVISIONS REQUIRED TO ACCOMMODATE A DEVIATION, WHETHER APPROVED BY THE ARCHITECT OR NOT, SHALL BE THE RESPONSIBILITY OF THE

16. THE GENERAL CONTRACTOR FOR THIS CONSTRUCTION IS RESPONSIBLE FOR THE COORDINATION, APPEARANCE, SCHEDULING, AND TIMELINESS OF THE WORK OF ALL TRADES, CONTRACTORS, SUPPLIERS,

THE GENERAL CONTRACTOR, MECHANICAL CONTRACTOR, AND ALL OTHER CONTRACTORS SHALL ENSURE PROPER COORDINATION BETWEEN ALL TRADES SUCH THAT CONDUITS, PIPING, DUCTWORK, ETC. DO NOT BLOCK ACCESS TO VALVES, EQUIPMENT, DUCT ACCESS DOORS, ETC. ITEMS THAT HAVE BEEN INSTALLED

18. THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL COSTS ASSOCIATED WITH DRAINING, FLUSHING, AND

. PRIOR TO ORDERING ANY MATERIALS OR ROUGH-IN OF ANY KIND, THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR FINAL COORDINATION OF ALL ELECTRICAL REQUIREMENTS (I.E., VOLTAGE, PHASE, CIRCUIT BREAKER, WIRING SIZE, ETC.) WITH THE ELECTRICAL CONTRACTOR. THERE WILL BE NO CHANGE IN THE CONTRACT AMOUNT FOR ANY DISCREPANCIES. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ALL OTHER CONTRACTORS, VENDORS, AND SUPPLIERS AND SHALL INSURE COMPLETE, 100% FUNCTIONAL TESTED, INSPECTED, AND APPROVED SYSTEMS. CLAIMS FOR ADDITIONAL COST OR CHANGE ORDERS WILL

20. EQUIPMENT BRACING WILL BE INCLUDED FOR ALL OVERHEAD UTILITIES AND OTHER EQUIPMENT WEIGHING 31 POUNDS OR MORE (EXCLUDING DISTRIBUTED SYSTEMS SUCH AS PIPING, ETC.). BRACING SHALL BE ACCOMPLISHED BY EITHER RIGID OR FLEXIBLE SYSTEMS. ALL EQUIPMENT MOUNTINGS SHALL BE DESIGNED TO RESIST FORCES OF 0.5 TIMES THE EQUIPMENT WEIGHT IN ANY DIRECTION AND 1.5 TIMES THE EQUIPMENT

OR PLAN DOR PLAN JLES & DETAILS ST FLOOR PLAN ID FLOOR PLAN EL PLAN AGRI-CENTER BLDG ELECTRICAL LOWER LEVEL PLAN

HVAC UPGRADES LAUDERDALE COUNTY MERIDIAN, MISSISSIPPI


> CONSTRUCTION DOCUMENTS OCTOBER 4, 2022

PROJECT MAP



HUMAN SERVICES BUILDING PROJECT LOCATION

EMERGENCY SERVICES / EMA -PROJECT LOCATION





AGRI-CENTER PROJECT LOCATION

5 **ENGINEERING RESOURCE GROUP** 350 EDGEWOOD TERRACE DRIV JACKSON, MS 39206 PHONE: (601) 362-3552 FAX: (601) 366-6418

CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

Ш́О

PROJECT:

SIP S N S Ξ **RIDIA** \mathcal{O} \mathbb{R} Ш \geq


Λ

PROJECT NUMBER: 22.006 DATE: 10/4/2022 DRAWN BY: KAH CHECKED BY: CEM REV: 0 IFC 10/4/2022 SEAL SHEET TITLE:

TITLE SHEET

SHEET NUMBER


T0.1



																				MEETII ROOM 140	NG
0]												<u>E 139</u>		X		X			 	
					X							×									
) /132			133			134		143			144			145				146			
<u>126</u>			<u>128</u>			<u>127</u>			50			<u>9</u>		<u>148</u>				147		-	
<u>124</u>			<u>125</u>	X		<u>126</u>			<u>31</u>			<u>2</u>		<u>153</u>				$\frac{PRIN}{154}$	TER M		
																					159
					e											<u> </u>					160
							CLER	CAL AREA	<u>A</u>]	
J 																	7				
				2	X		X														
		×.																X			

FIRST FLOOR CEILING PLAN SCALE:3/16" = 1'-0"








CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

 $\langle x \rangle$

MISSISSIPPI OUNT S RADE Ö C JP(AL HVAC U LAUDERD/ MERIDIAN,

PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	22




SHEET TITLE:


HUMAN SERVICES -FIRST FLOOR CEILING PLAN

SHEET NUMBER

A1.1







GENERAL NOTES:

- A. DEMO EXISTING CEILING TILE AND GRID.
- B. NEW 2x2 CEILING IS TO MATCH EXISTING CEILING HEIGHT.
- C. SALVAGE IS DEFINED AS CAREFULLY REMOVING & RETAINING ITEMS FOR REUSE. FURTHER EVALUATION OF CERTAIN ITEMS IN TERMS OF SALVAGE DESIRABILITY MAY OCCUR PRIOR TO DEMOLITION.
- D. IF ANY FIREPROOFING OR ASSEMBLIES WHICH ARE INDICATED TO REMAIN ARE DAMAGED DURING DEMOLITION THE CONTRACTOR SHALL REPAIR DAMAGE TO THE LEVEL OF THE ORIGINAL FIRE PROTECTION REQUIREMENTS.
- E. MAINTAIN, WHERE POSSIBLE, ALL FIRE ALARM DEVICES, SPEAKERS, ETC. AND PROVIDE COVERS TO PROJECT DEVICES FROM DUST AND DEBRIS. WHERE DEVICES CANNOT BE MAINTAINED, REMOVE DEVICES AND STORE TO PREVENT DAMAGE. RE-INSTALL DEVICES ONCE CEILING HAS BEEN INSTALLED.

PLAN NOTES:

1. ALL EXISTING CEILINGS TO BE REMOVED FOR DUCTWORK AND PIPING DEMOLITION. SALVAGE LIGHT FIXTURES, CEILING SPEAKERS, PROJECTORS, FIRE ALARM DEVICES, ETC. AND REINSTALL DURING RENOVATION PHASE. PROVIDE NEW GRID SYSTEM AS REQUIRED FOR NEW 2x2 TILE SYSTEM.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

 $\langle \mathbf{x} \rangle$

PROJECT:

MISSISSIPP RADES COUNT JPGI MERIDIAN, HVAC U LAUDERD


PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/2</u> 1 2 3	022
SEAL	


SHEET TITLE:

HUMAN SERVICES SECOND FLOOR CEILING PLAN

SHEET NUMBER

A1.2








CONSTRUCTION DOCUMENTS

A1.3

SHEET NUMBER





LOWER RESTROOMS CEILING PLAN SCALE: 1/4" = 1'-0"

GENERAL NOTES:

- A. NEW CEILING IS TO MATCH EXISTING CEILING HEIGHT.
- B. SALVAGE IS DEFINED AS CAREFULLY REMOVING & RETAINING ITEMS FOR REUSE. FURTHER EVALUATION OF CERTAIN ITEMS IN TERMS OF SALVAGE DESIRABILITY MAY OCCUR PRIOR TO DEMOLITION.
- C. IF ANY FIREPROOFING OR ASSEMBLIES WHICH ARE INDICATED TO REMAIN ARE DAMAGED DURING DEMOLITION THE CONTRACTOR SHALL REPAIR DAMAGE TO THE LEVEL OF THE ORIGINAL FIRE PROTECTION REQUIREMENTS.
- D. MAINTAIN, WHERE POSSIBLE, ALL FIRE ALARM DEVICES, SPEAKERS, ETC. AND PROVIDE COVERS TO PROJECT DEVICES FROM DUST AND DEBRIS. WHERE DEVICES CANNOT BE MAINTAINED, REMOVE DEVICES AND STORE TO PREVENT DAMAGE. RE-INSTALL DEVICES ONCE CEILING HAS BEEN INSTALLED.

PLAN NOTES:

- 1. EXISTING CEILINGS TO BE REMOVED FOR DUCTWORK AND PIPING DEMOLITION. SALVAGE LIGHT FIXTURES, CEILING SPEAKERS, FIRE ALARM DEVICES, ETC. AND REINSTALL DURING RENOVATION PHASE.
- 2. PROVIDE AND INSTALL A MINIMUM OF R19 INSULATION ABOVE CEILING LAT CEILING.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

 $\langle X \rangle$

PROJECT:

: UPGRADES RDALE COUNTY MISSISSIPPI F Ζ HVAC I LAUDERE MERIDIAN

PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/202</u> 1 2 3	
SEAL	

SHEET TITLE: ARGI-CENTER - LOWER **RESTROOMS CEILING** PLAN - ADD ALT. #1

SHEET NUMBER

A1.4

HVAC LEGEND AND ABBREVIATIONS

IIVACI											
PIPING LEGEND PIPING LEGEND (CONT.)			DU	CTWORK LEGEND	CONTROLS LEGEND			REVIATIONS - MECHANICAL	ABBREVIATIONS - MECHANICAL		
→ Ĩ	CONCRETE THRUST BLOCK		TOP PIPE CONNECTIONS		RADIUS ELBOW	CO	CARBON MONOXIDE SENSOR	ACU	AIR CONDITIONING UNIT	LAT	LEAVING AIR TEMPERATURE
• 	FLOW METER					603	CARBON DIOXIDE SENSOR	AD	ACCESS DOOR	LBS	POUNDS
EM		<u>∽ - C-C</u>	SLOPED CHANGE IN		ELBOW WITH TURNING VANES	H	HUMIDITY SENSOR	AHU	AIR HANDLING UNIT	LD	LINEAR DIFFUSER (CEILING, WALL, SILL OR FLOOR)
FS	FLOW SWITCH		PIPE ELEVATION			T	THERMOSTAT	BMS	BUILDING MANAGEMENT SYSTEM	LRA	LOCK ROTOR AMPS
	FIRESTOPPING				RECTANGULAR BRANCH TAKEOFF WITH BALANCING	TP	PROGRAMMABLE THERMOSTAT	BHP	BRAKE HORSE POWER	LFD	LOUVER FACE DIFFUSOR
	PIPE SLEEVE		SHUT-OFF VALVE		DAMPER	S	TEMPERATURE SENSOR	BTU	BRITISH THERMAL UNIT	LWT	LEAVING WATER TEMPERATURE
<u>} </u>			AUTOMATIC FLOW		RECTANGULAR SUPPLY	WS	WALL SWITCH	СС	COOLING COIL	MA	MIXED AIR
└──┤	BEAM PENETRATION		CONTROL VALVE		DUCT UP	RC	REMOTE CONTROLLER	CD	CEILING DIFFUSER	MAT	MIXED AIR TEMPERATURE
<u>,</u>	PIPE CAP		MEASURING DEVICE		RECTANGULAR SUPPLY DUCT DOWN	T/C	TIME CLOCK	CER CRG	CEILING EXHAUST REGISTER	MAX	
<u> </u>	PIPE BLIND FLANGE		VENTURI TYPE FLOW MEASURING DEVICE			ESS	HVAC SYSTEM EMERGENCY SHUT-OFF BUTTON	CFM		MBH MFG	THOUSAND BTU PER HOUR
, , , , , , , , , , , , , , , , , , , ,			BALL VALVE WITH HOSE		RECTANGULAR RETURN OR EXHAUST DUCT UP		WALL OR CEILING MOTION HEAT SENSOR	СТБ	CEILING TRANSFER GRILLE	MFG	MANUFACTURER MAXIMUM FUSE SIZE
} ► {	HOT WATER FLOW DESIGNATION	<u>ዮ</u>	THREAD CONNECTION			EMCS	ENERGY MANAGEMENT AND CONTROL SYSTEM	CG	CEILING GRILLE	MIN	MINIMUM
├── HWS → ╎ ├── HWS → }	HOT WATER SUPPLY		040.000//		RECTANGULAR RETURN OR EXHAUST DUCT DOWN			со	CLEAN OUT	MUA	MAKE UP AIR UNIT
<u>}</u> HWR ←	HOT WATER RETURN		GAS COCK				MISCELLANEOUS	CRA	CONDITIONING RETURN AIR	MOCP	
					ROUND DUCT, UP			CSA	CONDITIONING SUPPLY AIR	NC	PROTECTION NORMALLY CLOSED
└── G ─── └	GAS (NATURAL) GAS (PROPANE)		BALANCING VALVE	—			DIFFERENTIAL PRESSURE SENSOR	СТ	COOLING TOWER	NFA	NET FREE AREA
└── RS ── \ └── RL ── \	REFRIGERANT SUCTION REFRIGERANT LIQUID			<u>آ</u>	ROUND DUCT, DOWN	┍╴┲╸┑	DIFFERENTIAL PRESSURE SWITCH	DB	DRY BULB	NIC	NOT IN THIS CONTRACT
∽ HL →	HIGH PRESS. LIQUID	∽⊣€⊢⊰	GLOBE VALVE	<u></u>	SLOPING RISE IN DUCTWORK	Ø	DIAMETER	DG	DOOR GRILLE	NO	NORMALLY OPEN
S→→ HV→S S→→ LV→S	HIGH PRESS. VAPOR LOW PRESS. VAPOR					٣		DIA	DIAMETER	NTS	NOT TO SCALE
	ARROW INDICATES DIRECTION OF FLOW		CHECK VALVE	┝╼ <u></u> <u></u> <u></u> <u></u> <u></u>	SLOPING DROP IN DUCTWORK	HW		DN	DOWN	OA	OUTSIDE AIR INTAKE
· · · · · · · · · · · · · · · · · · ·	PITCH PIPE DOWN IN						RISER DESIGNATION	DX	DIRECT EXPANSION	OBD	OPPOSED BLADE DAMPER
	DIRECTION OF ARROW		AUTOMATIC THREE-WAY CONTROL VALVE	> 18x12 <	DUCT SIZE (CLEAR INSIDE DIMENSION) FIRST FIGURE INDICATES PLAN SIZE	2 M3.1	SECTION NUMBER	EA	EXHAUST AIR	OD	OUTSIDE DIMENSION
← D ← ∽	CONDENSATE DRAIN LINE	<u> </u>				M3.1	DRAWING NUMBER	EAT	ENTERING AIR TEMPERATURE	Р	PUMP
<u>, ⊥</u> , ,			AUTOMATIC TWO-WAY CONTROL VALVE		ROUND DUCT DIAMETER SIZE (CLEAR INSIDE DIMENSION)		DETAIL NUMBER	EDB	ENTERING DRY BULB	PD	PRESSURE DROP
	PIPE GUIDE	3		2 18 φ ζ	(CLEAR INSIDE DIVIENSION)	(<u>1</u>) M2.1	DETAIL DESIGNATION	EF	EXHAUST FAN	RA	RELEIF AIR
	EXPANSION COMPENSATOR	ا ب⊣ ⁰ ⊢۔، ۶	RELIEF VALVE	<u>, 18/12</u>	OVAL DUCT SIZE		EQUIPMENT TYPE	EFF	EFFICIENCY	RH	RELATIVE HUMIDITY
\leftarrow				2 18/12	OVAL DUCT SIZE	CT 1-1	EQUIPMENT NUMBER	ET	EXPANSION TANK	RHC	REHEAT COIL
	(INCREASER)		ANGLE RELIEF VALVE		SIDE, TOP OR BOTTOM DUCT		EQUIPMENT DESIGNATION	EWB	ENTERING WET BULB	RPM	REVOLUTIONS PER MINUTE
	(INCREASER)				ACCESS DOOR		3.24	EWT		RP	RECIRC PUMP
	UNION		PRESSURE REDUCING VALVE (PRV)		RECTANGULAR OR SQUARE TO ROUND OR OVAL TRANSITION	T-3.24	SYSTEM	°F FC	DEGREES FAHRENHEIT FLEXIBLE CONNECTION (DUCT OR	SA	SUPPLY AIR
	CAPPED PIPE WITH	$\rightarrow \rightarrow \rightarrow$	LUBRICATED		DOUBLE-WALL DUCT IS INDICATED BY SHADING		VAV TERMINAL UNIT DESIGNATION	FD	PIPE) FUSIBLE LINK FIRE DAMPER W/	SD	
	SHUT-OFF VALVE		PLUG VALVE		INTERNALLY LINED DUCTWORK		1.01	FLR	DUCT ACCESS DOOR FLOOR	SENS SP	SENSIBLE STATIC PRESSURE
	"Y" TYPE STRAINER WITH HOSE END BLOW OFF		SOLENOID VALVE		IS INDICATED BY INSIDE DASHED LINE.	< <u>IDU-1.01</u> >	SYSTEM	FLA	FULL LOAD AMPS	SQFT	SQUARE FEET
	VALVE				FLEXIBLE DUCT		VRV INDOOR UNIT DESIGNATION	FT	FEET	ТА	TRANSFER AIR DUCT
	"Y" TYPE STRAINER		BUTTERFLY VALVE (MANUAL)				EXISTING EQUIPMENT, PIPING, OR	GF	GAS FURNACE	ТҮР	TYPICAL
					VOLUME DAMPER IN DUCT		DUCTWORK TO REMAIN IN SERVICE.	GPM	GALLONS PER MINUTE	VAV	VARIABLE AIR VOLUME
	ELBOW TURNED UP		BALL VALVE				EXISTING EQUIPMENT, PIPING, OR DUCTWORK TO BE REMOVE	GWH	GAS WATER HEATER	VD	VOLUME DAMPER
	ELBOW TURNED DOWN	Г			MOTORIZED DAMPER		NEW CONNECTION TO	нс	HEATING COIL	VFD	VARIABLE FREQUENCY DRIVE
<u>ک</u> (BOTTOM PIPE		BALL VALVE. NORMALLY CLOSED				EXISTING PIPING, DUCTWORK AND/OR EQUIPMENT	НР	HORSE POWER	VRF	VARIABLE REFRIGERANT FLOW
	CONNECTION				FIRE DAMPER			HR	HOUR	VSA	VENTILATION SUPPLY AIR
		<u>, - □ </u>	SIGHT GLASS		GRAVITY BACK DRAFT DAMPER	/OF	FUSER DESIGNATION AND LENGTH R NECK SIZE (LINEAR OR LOUVER	HRU	HEAT RECOVERY UNIT	VTR	VENT THRU ROOF
			MANUAL AIR VENT			10 10	FUSER ONLY) TTERN (4A UNLESS INDICATED	HWS	HEATING WATER SUPPLY	W/	WITH
))			SUPPLY DIFFUSR		HERWISE	HWR	HEATING WATER RETURN	WSR	WALL SUPPLY REGISTER
		<u>, Ŷħ</u> ,	AUTOMATIC AIR VENT					ID	INSIDE DIMENSION	WB	WET BULB
		<u>, </u>	THERMOMETER		LINEAR DIFFUSER	UIFFUSER, RE	TURN, & EXHAUST GRILLE TAG	KW	KILOWATT		
		, , , ,,	PIPE SENSOR WELL (THERMOMETER)		RETURN/EXHAUST REGISTER OR GRILLE						
		 ∽_ ``` ,	PRESSURE GUAGE AND COCK		FIRE RATED ENCASED DUCT						
		ф , ф	PRESSURE GUAGE WITH LOOP		SUPPLY REGISTER WITH AIR OUTLET DEVICE DESIGNATION						
		, P , ,	TEMPERATURE-PRESSURE TEST FITTING		RETURN OR EXHAUST REGISTER OR GRILLE WITH AIR INLET						
					DEVICE DESIGNATION						
					, _ , _						

1. EACH CONTRACTOR, SUPPLIER AND/OR MANUFACTURER SHALL REFER TO ALL DOCUMENTS PERTAINING TO THIS PROJECT AND COORDINATE ACCORDINGLY SO AS TO ENSURE ADEQUACY OF FIT, COMPLIANCE WITH SPECIFICATIONS, PROPER ELECTRICAL SERVICE, AND AVOID CONFLICT WITH ANY OTHER BUILDING SYSTEMS. VERIFY SAME WITH SHOP DRAWINGS.

- OSHA, ETC.).
- REMOVED AND REINSTALLED SATISFACTORILY.
- DRAWING REQUIREMENTS.
- SUPPLIED TO THE CONTRACTOR.
- SHALL MATCH ADJACENT SURFACES.
- KITCHEN EXHAUST DUCTS.

- CLARIFICATION BY WRITTEN ADDENDUM.
- RESPONSIBLE CONTRACTOR(S).
- SHALL BE THAT OF THE ARCHITECT.
- CLARIFICATION.
- IN WRITING.

- ADJUSTMENT BY THIS CONTRACTOR.

- EXPENSE.
- INSTALL THEIR NEW WORK.

- DRAWINGS AND SPECIFICATIONS.

GENERAL NOTES - HVAC

2. ALL OFFSETS, TURNS, FITTINGS, TRIM, DETAIL, ETC., MAY NOT BE INDICATED, BUT SHALL BE PROVIDED AS REQUIRED. ADDITIONAL ALLOWANCES SHALL BE INCLUDED FOR SAME AT EACH PROPOSERS' DISCRETION.

3. OBSERVE ALL APPLICABLE CODES, RULES AND REGULATIONS (CITY, COUNTY, LOCAL, STATE, FEDERAL, MUNICIPALITY, UTILITY COMPANY,

4. ALL SYSTEMS, EQUIPMENT, AND MATERIALS ARE TO BE INSTALLED IN A NEAT AN WORKMANLIKE MANNER. WORK NOT DONE SO SHALL BE

5. WHERE MOUNTING HEIGHTS ARE NOT INDICATED OR ARE IN CONFLICT WITH ANY OTHER BUILDING SYSTEM, CONTACT THE ENGINEER BEFORE INSTALLATION. REFER ALSO TO ARCHITECTURAL WALL INTERIOR AND EXTERIOR WALL ELEVATIONS, CEILING HEIGHTS AND OTHER DETAILS OF THESE DOCUMENTS. REFERENCE SPECIFICATION 230010 "MECHANICAL GENERAL PROVISIONS" FOR COORDINATION

6. DO NOT SCALE DRAWINGS, PRINTING DISTORTS SCALE. WORK SHALL BE LAID OUT FROM DIMENSIONED DRAWINGS, OR DIMENSIONS

7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CUTTING AND PATCHING REQUIRED FOR THEIR WORK, ALL CUTTING AND PATCHING

8. TURNING VANES SHALL BE INSTALLED IN ALL SUPPLY, RETURN, AND EXHAUST DUCTWORK ELBOWS. TURNING VANES NOT REQUIRED FOR

9. THESE DRAWINGS ARE ACCURATE TO THE BEST OF OUR KNOWLEDGE, HOWEVER LOCATIONS, DEPTHS, ELEVATIONS, AND SIZES WERE TAKEN FROM DIFFERENT SOURCES AND ARE SUBJECT TO DEVIATION. THE CONTRACTOR SHALL ASSUME SOME DEVIATIONS AND INCLUDE OFFSETS, ADDITIONAL PIPING, ETC. AT THE TIME OF BID.

10. WHERE PENETRATING ROOFING MEMBRANE OR OTHER MATERIALS USED FOR WEATHERPROOFING THE BUILDING, MAKE SUCH PENETRATIONS IN A WAY THAT WILL NOT VOID OR DIMINISH THE ROOFING WARRANTY OR INTEGRITY IN ANY WAY. COORDINATE ALL SUCH PENETRATIONS WITH THE GENERAL CONTRACTOR/ROOFER.

11. ADVISE THE ARCHITECT OF ANY CONFLICTS, ERRORS, OMISSIONS, ETC. AT LEAST TEN DAYS PRIOR TO BID DATE, TO ALLOW

12. DEVIATION FROM SPECIFICATIONS OR PLANS REQUIRES PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND MUST BE SUBMITTED IN WRITING NO LATER THAN TEN DAYS PRIOR TO THE BID DATE.

13. COORDINATE THE LOCATION OF DRAINS, ELECTRICAL OUTLETS, ETC. WITH ALL MECHANICAL ROOM EQUIPMENT, ETC. PRIOR TO COMMENCING INSTALLATION. WORK NOT SO COORDINATED SHALL BE REMOVED AND PROPERLY INSTALLED AT THE EXPENSE OF THE

14. THE PURPOSE AND INTENT OF THE DOCUMENTS PERTAINING TO THIS PROJECT IS TO PROVIDE A COMPLETE, FUNCTIONAL, AND SAFE FACILITY, ANYTHING LESS SHALL BE UNACCEPTABLE.

15. ALL VIBRATING, OSCILLATING, NOISE PRODUCING OR ROTATING EQUIPMENT SHALL BE ISOLATED FROM SURROUNDING SYSTEMS IN AN APPROVED MANNER. NOISY, VIBRATING, OR STRUCTURALLY DAMAGING INSTALLATIONS SHALL BE SATISFACTORILY REPLACED OR REPAIRED AT THE INSTALLING CONTRACTOR'S EXPENSE. THE FINAL DECISION ON THE SUITABILITY OF A PARTICULAR INSTALLATION

16. INSTALL EQUIPMENT, MATERIALS, ETC. IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND DIRECTIONS. IF IN CONFLICT WITH THE DESIGN INDICATED IN CONTRACT DOCUMENTS, ADVISE THE ARCHITECT PRIOR TO INSTALLATION FOR

17. ALL SUPPORTS FOR EQUIPMENT, DEVICES, OR FIXTURES SHALL BE UNIQUE FROM THE BUILDING STRUCTURE. DO NOT SUPPORT FROM OTHER TRADES, EQUIPMENT OR SUPPORTS WITHOUT WRITTEN PERMISSION FROM THE ARCHITECT AND CONSENT OF THE OTHER TRADE,

18. DEVIATIONS IN SIZE, CAPACITIES, FIT, FINISH, ETC. FOR EQUIPMENT FROM THAT SPECIFIED SHALL BE THE RESPONSIBILITY OF THE PURCHASER OF THAT EQUIPMENT. ANY PROVISIONS REQUIRED TO ACCOMMODATE A DEVIATION, WHETHER APPROVED BY THE ARCHITECT OR NOT, SHALL BE THE RESPONSIBILITY OF THE PURCHASER.

19. THE GENERAL CONTRACTOR FOR THIS CONSTRUCTION IS RESPONSIBLE FOR THE COORDINATION, APPEARANCE, SCHEDULING, AND TIMELINESS OF THE WORK OF ALL TRADES, CONTRACTORS, SUPPLIERS, INSTALLERS, ETC.

20. VALVES, BALANCING DAMPERS OR ANY MECHANICAL/ELECTRICAL ITEM SHALL NOT BE LOCATED ABOVE A HARD CEILING. IF THIS IS NOT POSSIBLE, THEN AN APPROPRIATELY SIZED ACCESS DOOR SHALL BE PLACED UNDER THE ITEM TO ALLOW EASY MAINTENANCE AND

21. PROVIDE FIRE DAMPERS AND APPROPRIATE DUCT ACCESS DOORS IN ALL DUCT PENETRATIONS WHERE REQUIRED BY CODE. CONTACT PROFESSIONAL SHOULD CLARIFICATION BY REQUIRED.

22. PROVIDE METAL SLEEVES AND FIRESTOPPING ON ALL DUCTWORK PASSING THRU RATED WALLS, PER CODE.

23. THE GENERAL CONTRACTOR, MECHANICAL CONTRACTOR, AND ALL OTHER CONTRACTORS SHALL ENSURE PROPER COORDINATION BETWEEN ALL TRADES SUCH THAT CONDUITS, PIPING, DUCTWORK, ETC. DO NOT BLOCK ACCESS TO VALVES, EQUIPMENT, DUCT ACCESS DOORS, ETC. ITEMS THAT HAVE BEEN INSTALLED WHERE ACCESS IS COMPROMISED SHALL BE RELOCATED AT THE CONTRACTOR'S

24. THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL COSTS ASSOCIATED WITH DRAINING AND FILLING PIPING SYSTEMS AS REQUIRED TO

25. TESTING, ADJUSTING, AND BALANCING AGENCY IS TO PROVIDE SIZING OF FAN AND MOTOR SHEAVES REQUIRED FOR PROPER BALANCE. REPLACE FAN AND MOTOR SHEAVES AND BELTS AS REQUIRED ON EQUIPMENT (AHUS, EFS, ETC.). THE MECHANICAL CONTRACTOR SHALL PURCHASE AND INSTALL ALL SHEAVES AND BELTS AS REQUIRED.

26. PRIOR TO ORDERING ANY MATERIALS OR ROUGH-IN OF ANY KIND, THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR FINAL COORDINATION OF ALL ELECTRICAL REQUIREMENTS (I.E., VOLTAGE, PHASE, CIRCUIT BREAKER, WIRING SIZE, ETC.) WITH THE ELECTRICAL CONTRACTOR. THERE WILL BE NO CHANGE IN THE CONTRACT AMOUNT FOR ANY DISCREPANCIES. MECHANICAL CONTRACTOR SHALL COORDINATE WITH ALL OTHER CONTRACTORS, VENDORS, AND SUPPLIERS AND SHALL INSURE COMPLETE, 100% FUNCTIONAL, TESTED, INSPECTED, AND APPROVED SYSTEMS. CLAIMS FOR ADDITIONAL COST OR CHANGE ORDERS WILL IMMEDIATELY BE REJECTED.

27. EQUIPMENT BRACING WILL BE INCLUDED FOR ALL OVERHEAD UTILITIES AND OTHER EQUIPMENT WEIGHING 31 POUNDS OR MORE (EXCLUDING DISTRIBUTED SYSTEMS SUCH AS PIPING, ETC.). BRACING SHALL BE ACCOMPLISHED BY EITHER RIGID OR FLEXIBLE SYSTEMS. ALL EQUIPMENT MOUNTINGS SHALL BE DESIGNED TO RESIST FORCES OF 0.5 TIMES THE EQUIPMENT WEIGHT IN ANY DIRECTION AND 1.5 TIMES THE EQUIPMENT WEIGHT IN THE DOWNWARD DIRECTION. ALL BRACING SHALL BE CONTRACTOR DESIGNED.

28. ALL BRANCH DUCTS TO AIR DISTRIBUTION DEVICES (SUPPLY, RETURN, EXHAUST, ETC.) SHALL INCLUDE A VOLUME DAMPER PER

29. DUCT SIZES INDICATED ARE ACTUAL INSIDE (NET) DIMENSIONS. ALL RECTANGULAR SUPPLY, RETURN, EXHAUST, AND OUTDOOR AIR DUCT SIZES ARE INSIDE CLEAR DIMENSIONS (INSIDE LINER, WHERE APPLICABLE).



CONSULTANTS: **ELECTRICAL ENGINEER** SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

SIP ADE S C Ω \square RIDIA C R ĂШ $\geq \Box$ \supset Ш

Ń

Σ

Σ


PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/2</u> 1 2 3	022
SEAL	

SHEET TITLE:

MECHANICAL LEGEND, ABBREVIATIONS, AND NOTES

SHEET NUMBER

M0.1





 EXISTING FAN COIL UNIT, DUCTWORK, AIR DISTRIBUTION DEVICE, PIPING, ETC. TO BE DEMOLISHED.

 $\langle x \rangle$

2. EXISTING CONDENSATE DRAIN PIPIING IN WALL TO REMAIN (FIELD-VERIFY). THIS CONTRACTOR IS TO MAKE NECESSARY MODIFICATIONS TO EXISTING PIPE ABOVE CEILING FOR CONNECTION OF NEW PIPING.

GENERAL NOTES:

 ALL EXISTING CONDENSATE PIPING ABOVE CEILING IS TO BE REMOVED UNLESS NOTED OTHERWISE.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

HVAC UPGRADES LAUDERDALE COUNTY MERIDIAN, MISSISSIPPI

PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/202</u> 1 2 3	
SEAL	


SHEET TITLE:

HUMAN SERVICES -FIRST FLOOR PLAN -HVAC DEMOLITION

SHEET NUMBER

CONSTRUCTION DOCUMENTS

M1.1





- EXISTING FAN COIL UNIT, DUCTWORK, AIR DISTRIBUTION DEVICE, PIPING, ETC. TO BE DEMOLISHED.
- 2. EXISTING CONDENSATE DRAIN PIPING IN WALL TO REMAIN (FIELD-VERIFY). THIS CONTRACTOR IS TO MAKE NECESSARY MODIFICATIONS TO EXISTING PIPE ABOVE CEILING FOR CONNECTION OF NEW PIPING.

 $\langle x \rangle$

GENERAL NOTES:

 ALL EXISTING CONDENSATE PIPING ABOVE CEILING IS TO BE REMOVED UNLESS NOTED OTHERWISE.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:




PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	
SEAL	


SHEET TITLE:

HUNAN SERVICES -SECOND FLOOR PLAN -HVAC DEMOLITION

SHEET NUMBER

M1.2





1. VSA DIFFUSER - SEE VENTILATION AND PIPING PLAN FOR DETAILS.

 $\langle X \rangle$



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

UPGRADES DALE COUNTY MISSISSIPPI HVAC U LAUDERD*i* MERIDIAN,

PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	22
SEAL	




SHEET TITLE:

HUMAN SERVICES -SECOND FLOOR PLAN -HVAC RENOVATION

SHEET NUMBER

M1.4



M1.5

MISSISSIPPI


MERIDIAN,

22.006

10/4/2022

KAH

CEM





CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

 $\langle x \rangle$

PROJECT:


MISSISSIPPI SRADES COUNTY JPGI AL MERIDIAN, HVAC U LAUDERD


PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	22
SEAL	



SHEET TITLE: HUMAN SERVICES -SECOND FLOOR PLAN -HVAC VENTILATION AND PIPING

SHEET NUMBER





1. REMOVE EXISTING CHILLER, BOILER, EXPANSION TANKS, PUMPS, PIPING, VALVES, ETC.


 \otimes

- EXISTING ZONE PIPING, HANGER, VALVES, ETC. TO BE REMOVED THOUGHT OUT THE ENTIRE BUILDING.
- 3. REFRIGERANT PIPE SUPPORT.





CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313


PROJECT:




PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	
SEAL	
SHEET TITLE: HUMAN SER ENLARGED MECHANICAI PLAN - HY	SCALE ROOM
SHEET NUMBER	
M1.	7









1. TRAP AND VENT CONDENSATE DRAIN (SEE DETAIL) AT INDOOR UNIT. INCREASE TO 1" AND RUN ABOVE CEILING.

X

- 2. TRAP AND VENT CONDENSATE DRAIN (SEE DETAIL) AT BC CONTROLLER. INCREASE TO 1" AND RUN ABOVE CEILING.
- 3. EXISTING CONDENSATE DRAIN DOWN IN WALL
- (FIELD-VERIFY) EXACT LOCATION. 4. NEW CONDENSATE PIPE (SEE PLANS FOR PIPE SIZE). CONNECT TO EXISTING CONDENSATE PIPING ABOVE CEILING (FIELD-VERIFY) EXACT LOCATION.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313


PROJECT:


MISSISSIP OUNT \mathcal{O} ADE Ŭ Ц 4 MERIDIAN, HVAC U LAUDERD


PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/2</u> 1 2 3	2022
SEAL	R

SHEET TITLE: HUMAN SERVICES -SECOND FLOOR PLAN -HVAC CONDENSATE RENOVATION

SHEET NUMBER







ENLARGE MECHANICAL ROOM PLAN - HVAC RENOVATION (CONDENSATE)



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PLAN NOTES:

OWNER.


- 1. TRAP AND VENT CONDENSATE DRAIN (SEE DETAIL) AT PACKAGE UNIT. RUN DRAIN FULL-SIZE AND SPILL INTO HUB DRAIN.
- 2. 2" GAS. CONNECT TO EXISTING. DROP AND RUN BELOW GRADE.
- EXISTING GAS. METER AND REGULATOR.
 VERIFY EXISTING GAS METER AND REGULATOR WILL HANDLE ADDITIONAL 300 CFH, REPLACE IF NECESSARY AT NO ADDITIONAL COST TO THE OVERTICE
- PROJECT:


SRADES E COUNTY MISSISSIPPI JPGI MERIDIAN, HVAC U LAUDERD

PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	
SEAL	


MECHANICAL ROOM PLAN - HVAC CONDENSATE


SHEET NUMBER







FIRST FLOOR PLAN - HVAC DEMOLITION SCALE: 1/8" = 1'-0"









FIRST FLOOR PLAN - HVAC RENOVATION






AHU SECTION DESCRIPTION

- A. MIXING BOX AND FILTER SECTION W/1" TEST PORT & VALVE, LED MARINE LIGHT
- B. DX COOLING COIL W/STAINLESS STEEL DRAIN PAN. PIPING CONNECTION ON EXTERIOR OF UNIT, LED MARINE LIGHT.
- C. SUPPLY FAN SECTION, (2) DIRECT-DRIVE PLENUM FANS AND DISCHARGE SECTION W/1" TEST PORT & VALVE, WINDOW, LED MARINE LIGHT. EACH SUPPLY FAN SHALL BE FACTORY WIRED FROM THE FAN MOTOR TO A FACTORY INSTALLED EXTERNAL JUNCTION BOX. ELECTRICAL SERVICE TO EACH FACTORY WIRED EXTERNAL JUNCTION BOX IS SPECIFIED UNDER DIVISION 26 ELECTRICAL.








\ DETAIL OF MODULAR AHU-1 2

M4.1 SCALE: 1/2" = 1'-0"

AIR HAN	NDLING UNIT SOL	JND LIMIT	SCHEDU	JLE				
					MAXIMUM	Lw IN dB re 1	0 ⁻¹² WATTS	
TAG	SOURCE			00	CTAVE BAND	CENTER FR	EQUENCY -	Hz
		63	125	250	500	1000	2000	4000
AHU	DISCHARGE	86	84	92	87	88	88	87
	INLET	77	79	85	76	73	77	77
	CASING RADIATED	86	83	85	81	84	66	54








PLAN NOTES:

1. REMOVE EXISTING AHU AND WALL MTD VFD. EXISTING REFRIGERANT PIPING TO REMAIN FOR REUSE - MODIFY PIPING WITH NEW FITTING AS REQUIRED UNDER NEW WORK.

 $\langle \! \times \! \rangle$

2. PROVIDE AND INSTALL NEW AHU. RECONNECT TO EXISTING DUCTWORK, REFRIGERANT PIPING, ELECTRICAL SERVICE, PIPING, - MODIFY AS REQUIRED. CONTRACTOR IS TO RECONNECT ALL DUCT CONNECTION TO NEW AHU. TRAP AND VENT CONDENSATE AND RUN TO EXISTING FLOOR.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

RADES COUN⁻

UPGR/ DAI E 1

HVAC I

PROJECT NUMBER:

DRAWN BY:

CHECKED BY:

REV: 0 IFC 10/4/2022

SHEET TITLE: EMERGENCY

SHEET NUMBER

SERVICES / EMA -ENLARGED SCALE

MECHANICAL ROOM

PLAN - HVAC

M1.13

DATE:

SEAL

Δ

MISSISSIP


MERIDIAN


22.006

KAH

CEM


10/4/2022







UPPER RESTROOMS PLAN - HVAC DEMOLITION SCALE: 1/8" = 1'-0"

UPPER RESTROOMS PLAN - HVAC RENOVATION SCALE: 1/8" = 1'-0"











LOWER RESTROOMS PLAN - HVAC DEMOLITION


LOWER RESTROOMS PLAN - HVAC RENOVATION SCALE:1/4" = 1'-0"

PLAN NOTES:

1. EXISTING THRU WALL UNIT TO BE REMOVED. PATCH SURFACE TO MATCH.

 \otimes

- 2. EXISTING EXHAUST FAN TO BE REPLACED.
- 3. EXISTING ELECTRIC WALL HEATER TO BE REMOVED. PATCH SURFACE TO MATCH
- EXISTING.
- 4. PROVIDE WALL MOUNT BRACKET KIT FOR OUTDOOR UNIT. ROUTE REFRIGERANT PIPING UP WALL TO ABOVE CEILING AND RUN TO INDOOR UNIT. ALL REFRIGERANT PIPING (INDOOR AND OUTDOOR EXPOSED) TO HAVE PAINTABLE LINE HIDE.
- 5. SUSPENDED DEHUMIDIFIER FROM STRUCTURAL. PROVIDE UNIT FULL SIZE SECONDARY DRAIN PAN WITH OVER FLOW PROTECTION DEVICE TO SHUT OFF UNIT.
- 6. PUMP CONDENSATE TO NEAREST WASTE WITH DEEP SEAL TRAP.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:


COUNTY MISSISSIPPI Ś HVAC I LAUDERD MERIDIA


PROJECT	22.006
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:_	KAH
CHECKED BY	/: <u>CEM</u>
1 2	0/4/2022
/ Jul	E. MO PROF SINCER 0102 2022 SP
SHEET TITLE	:
	TER - LOWER


RESTROOMS PLAN HVAC


SHEET NUMBER


M1.12











ENGINEERING **RESOURCE GROUP** 350 EDGEWOOD TERRACE DRIVE JACKSON, MS 39206 PHONE: (601) 362-3552 FAX: (601) 366-6418

Ω

SIP

S N S

MIS

MERIDIAI

22.006

KAH

CEM


10/4/2022


SHEET NUMBER


CONSTRUCTION DOCUMENTS

M5.2

MECHANICAL DETAILS







RESOURCE GROUP 350 EDGEWOOD TERRACE DRIVE JACKSON, MS 39206 PHONE: (601) 362-3552 FAX: (601) 366-6418 CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313 PROJECT: Δ SIP SIS: \cap MIS () Δ 7 HVAC (UDERD MERIDIA PROJECT 22.006 NUMBER: 10/4/2022 DATE: DRAWN BY: KAH CHECKED BY: CEM REV: 0 IFC 10/4/2022 SEAL SHEET TITLE: MECHANICAL DETAILS SHEET NUMBER

5

ENGINEERING

CONSTRUCTION DOCUMENTS

M5.3

							OUTDOOR U	UNIT									INC	OOR UNIT							
	MANUFACTURER	AMBIENT	TEMP. (°F	С	APACITY (N	MBH)		ELEC	CTRICAL DATA		EFFICIENCY	WEIGHT	r			INDOOR A	R TEMP. (°F) MIN CA	PACITY (MBH)		ELECTRICAL DA	ATA	DUCTED UNIT	WEIGH	т
	AND MODEL NO.	SUMMER DB WB	WINTE DB	R COO		EATING	NO. OF MODULES	VOLT/	/Ø MCA	MOCP	IEER COP (47°) SCHE	(LBS)	' TAG	TYPE	BASIS OF DESIGN	SUMMER DB WE			G HEATING	VOLT/Ø	MCA	МОСР	SA OA	(LBS)	
													(IU-1.01)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65		,	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-1.02)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-1.03)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP024AM141A	78 65	70.	0 24.0	27.0	208/1	3.00	15	700	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-1.04)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-1.05)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
/())))))	TRANE-MITSUBISHI								1@43	1@70	23.3 3.4 22.7	1160	(IU-1.06)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP024AM141A	78 65	70.	0 24.0	27.0	208/1	3.00	15	700	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
	TURYP2163BN40AN (HEAT RECOVERY)	95 70	47	43 2	16.0	243.0	2	208/3	1@33	1@50	(DUCTED) (DUCTED) (DUCTED)	TOTAL	(U-1.07)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.	0 18.0	20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-1.08)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.	0 18.0	20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-1.09)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP048AM141A	78 65	70.	0 48.0	54.0	208/1	5.60	15	1400	180	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-1.10)	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP005FM140A	78 65	70.	0 5.0	5.6	208/1	0.24	15	280	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
													(IU-1.11)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-1.12)	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP012FM140A	78 65	70.	0 12.0	13.5	208/1	0.29	15	330	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
													(U-1.13)	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP005FM140A	78 65	70.	0 5.0	5.6	208/1	0.24	15	280	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
													(U-1.14)	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP005FM140A	78 65	70.	0 5.0	5.6	208/1	0.24	15	280	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
																	_		_					_	
													(U-2.01)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.	0 18.0	20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-2.02)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.0	0 18.0	20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-2.03)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP024AM141A	78 65			27.0	208/1	3.00	15	700	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-2.04)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP024AM141A	78 65	10.		27.0	208/1	3.00	15	700	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
	TRANE-MITSUBISHI												(IU-2.05)			78 65			27.0	208/1	3.00	15	700	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-31-BAS MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
T	TURYP2163BN40AN (HEAT RECOVERY)	95 70	47	43 2 ⁻	16.0	243.0	2	208/3	/3 1@43 1@33	1@70 1@50	23.3 3.4 22.7 (DUCTED) (DUCTED) (DUCTED)	1160 TOTAL	(IU-2.06)		TRANE-MITSUBISHI TPVFYP012AM141A	78 65			13.5	208/1	3.00	15	400	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
	(HEAT RECOVERT)									-			(IU-2.07)			78 65	10.		20.0	208/1	3.00	15	580	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													(IU-2.08)			78 65			27.0	208/1	3.00	15	700	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													(U-2.09)			78 65			54.0	208/1	5.60	15	1400	180	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													10-2.10	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.0	0 12.0	13.5	208/1	3.00	15	400	120	MTD IN FAN SECTION AND FILTER RACK
													(IU-3.01)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.0	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													(IU-3.02)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65			20.0	208/1	3.00	15	580	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													(IU-3.03)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65			20.0	208/1	3.00	15	580	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													(IU-3.04)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65			20.0	208/1	3.00	15	580	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													(IU-3.05)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP024AM141A	78 65			27.0	208/1	3.00	15	700	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS
													(IU-3.06)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.0		20.0	208/1	3.00	15	580	120	MTD IN FAN SECTION AND FILTER RACK R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
// 11 11 1 \ 1	TRANE-MITSUBISHI TURYP2403BN40AN	95 70	47	43 24	40.0	270.0	2	208/3	/3 1@43	1@70	22.3 3.3 22.9 (DUCTED) (DUCTED) (DUCTED)	1200	(IU-3.07)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65			20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
	(HEAT RECOVERY)								1@43	1@70		TOTAL	(U-3.08)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-3.09)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.0	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-3.10	AIR HANDLER	TRANE-MITSUBISHI TPVFYP030AM141A	78 65	70.	0 30.0	34.0	208/1	4.10	15	870	150	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-3.11)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP030AM141A	78 65	70.	0 30.0	34.0	208/1	4.10	15	870	150	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-3.12)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.	0 18.0	20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-3.13)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-4.01)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-4.02)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	70.	0 12.0	13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-4.03)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.	0 18.0	20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-4.04)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP018AM141A	78 65	70.0	0 18.0	20.0	208/1	3.00	15	580	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-4.05)	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP005FM140A	78 65	70.	0 5.0	5.6	208/1	0.24	15	280	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
T	TRANE-MITSUBISHI TURYP1923BN40AN	95 70	47	43 19	92.0	215.0	2	208/3	/3 2@33.0	2@50.0	24.3 3.6 23.0 (DUCTED) (DUCTED) (DUCTED)	1160	(IU-4.06)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP030AM141A	78 65	70.	0 30.0	34.0	208/1	4.10	15	870	150	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
	(HEAT RECOVERY)								S EACH	EACH	(DUCTED) (DUCTED) (DUCTED)		10-4.07	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP005FM140A	78 65	70.	0 5.0	5.6	208/1	0.24	15	280	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
													(U-4.08)	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP012FM140A	78 65	70.		13.5	208/1	0.29	15	330	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
													(U-4.09)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	10.		13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(U-4.10)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP054AM141A	78 65	70.		60.0	208/1	5.60	15	1480	180	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-4.11)	AIR HANDLER	TRANE-MITSUBISHI TPVFYP012AM141A	78 65	10.		13.5	208/1	3.00	15	400	120	R410A, PROVIDE W/GLOBAL PLASMA GPS-FC-3T-BAS MTD IN FAN SECTION AND FILTER RACK
													(IU-4.12)	CEILING CASSETTE	TRANE-MITSUBISHI TPLFYP005FM140A	78 65	70.	0 5.0	5.6	208/1	0.24	15	280	35	R410A, PROVIDE W/GLOBAL PLASMA GPS-IRIB
											FLOW PROTECTION DEVICE SWITCH.														

NOTE: ALL OUTDOOR UNIT TO BE PROVIDE WITH SUPER STAND. ALL DUCTED UNITS TO BE PROVIDE WITH SECONDARY DRAIN PAN AND OVERFLOW PROTECTION DEVICE SWITCH. PROVIDE TOUCH SCREEN BACNET GATEWAY.

BRAN	NCH SELECTOR S	CHEDULE						
TAG	MANUFACTURER AND MODEL NO.	SERVES	# PORTS	V - Ø	MCA	МОСР	OPERATING WEIGHT (LBS)	REMARK
BS 1-1	TRANE MITSUBISHI TCMBM1016JA11N4		16	208 - 1	1.5	15.0	150	R 410A R INFORM
BS 2-1	TRANE MITSUBISHI TCMBM1012JA11N4		12	208 - 1	1.5	15.0	150	R 410A R INFORM
BS 3-1	TRANE MITSUBISHI TCMBM1016JA11N4		16	208 - 1	1.5	15.0	150	R 410A R INFORM
BS 4-1	TRANE MITSUBISHI TCMBM1016JA11N4		16	208 - 1	1.5	15.0	150	R 410A F INFORM

RKS

A REFRIGERANT, CAP UNUSED PORTS, SEE BS CONTROLLER DETAILS FOR MORE RMATION, PROVIDE FULL PORT SCHRAEDER VALES ON ALL PIPING.

A REFRIGERANT, CAP UNUSED PORTS, SEE BS CONTROLLER DETAILS FOR MORE RMATION, PROVIDE FULL PORT SCHRAEDER VALES ON ALL PIPING.

A REFRIGERANT, CAP UNUSED PORTS, SEE BS CONTROLLER DETAILS FOR MORE RMATION, PROVIDE FULL PORT SCHRAEDER VALES ON ALL PIPING.


DA REFRIGERANT, CAP UNUSED PORTS, SEE BS CONTROLLER DETAILS FOR MORE RMATION, PROVIDE FULL PORT SCHRAEDER VALES ON ALL PIPING.



CONSULTANTS: <u>ELECTRICAL ENGINEER</u> SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

HVAC UPGRADES LAUDERDALE COUNTY MERIDIAN, MISSISSIPPI



SHEET TITLE:

HUMAN SERVICES -MECHANICAL SCHEDULES

SHEET NUMBER

M6.1

DED	ICATED OUT	DOOR AIR	SYSTE	EM SCH	HEDU	ILE																							
	MANUFACTURER			SUF	PPLY FAN					coc	DLING										HEATIN	١G			ELI	ECTRICAL	0	PER	
TAG	& MODEL NO.	SERVES	REFR TYPE	SUPPLY	ESP	ЦП	EDB	LDB	CAPACIT	⁻Y (MBH)	MIN	MIN	COM	IPRESS	OR	COND	ENSER		INPUT				MIN EFF	HGRH		мса мос	· ·	WT	REMARKS
	(TON)			CFM	ESP		EWB	LWB	TOTAL	SENS	EER	IEER	QTY	RLA	LRA	QTY	FLA		(MBH	l) (M	IBH)	FUEL	(%)	(MBH)	VOLI/Ø		P (L	LBS)	
DOAS	TRANE VALENT	BUILDING	R-410A	2400	1.0	1 5	95.6	53.7	229.6	111.2			1@	32.3	-		- EA	22	300		240	NAT	80.0	02.0	208/3	84.2 110.	.0 3	500	PAINTED EXTERIOR, DOUBLE WALL 2" R13 INJECTED FOAM INSULATED C
1	VX-212-17.5I-J-F0	BUILDING	R-410A	2400	1.0	1.5	79.8	53.6	229.0	111.2	-	-	1@	27.6	191	-			300		240	GAS	80.0	92.9	200/3	04.2 110.	.0 3	500	COMPRESSOR WITH A 5 YEAR WARRANTY, MODULATING NATURAL GAS F DUCT CONNECTION, WEATHER HOOD, 2" PLEATED MERV 8 FILTER, HOT (
																				·						· ·			HAIL GUARDS, HINGED ACCESS PANELS, NON-FUSED DISCONNECT, POW ADDITION), REMOTE CONTROLLER, VAPOR TIGHT LIGHT

POW	ER VENTILA	TOR SCH	HEDI	JLE									
TAG	MANUFACTURER	TYPE	CFM	ESP	RPM	SOUND	E	LECTRIC	AL	ON/OFF	INTERLOCK	OP WT	REMARKS
IAG	AND MODEL NO.	ITPE		LOF		(dBA/SONES)	BHP	HP	V/Ø		INTEREOCK	(LBS)	
EF 1	COOK GC-148	CEILING MOUNTED	70	0.25	763	0.9		31W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM
EF 2	COOK GC-622	CEILING MOUNTED	280	0.25	1044	1.3		89W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM
EF 3	COOK GC-186	CEILING MOUNTED	150	0.375	875	3.0		69W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM
$\left\langle \begin{array}{c} EF \\ 4 \end{array} \right\rangle$	COOK GC-148	CEILING MOUNTED	75	0.25	763	0.9		31W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM
EF 5	COOK GC-148	CEILING MOUNTED	70	0.25	763	0.9		31W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM
EF 6	COOK GC-622	CEILING MOUNTED	280	0.25	1044	1.3		89W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM
EF 7	COOK GC-186	CEILING MOUNTED	150	0.375	875	3.0		69W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM
EF 8	COOK GC-186	CEILING MOUNTED	150	0.375	875	3.0		69W	115/1	MOTION DETECTOR	NONE	-	PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAM

ED CABINET, DIRECT-DRIVE FANS WITH FACTORY MOUNTED VFDS, INVERTER SCROLL LEAD GAS FURNACE WITH 12:1 MODULATING TURNDOWN AND A 25 YEAR HX WARRANTY, HORIZONTAL SUPPLY HOT GAS REHEAT, UNIT SHALL PROVIDE ASHRAE 90.1 VENTILATION AIR HEATING CONTROL SEQUENCE, POWERED GFI OUTLET, OUTDOOR AIR DAMPER (LOW-LEAKAGE DAMPER PER ASHRAE 90.1-CURRENT

DAMPER, ISOLATOR KIT, WHITE ALUMINUM GRILLE
DAMPER, ISOLATOR KIT, WHITE ALUMINUM GRILLE



CONSULTANTS: <u>ELECTRICAL ENGINEER</u> SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

HVAC UPGRADES LAUDERDALE COUNTY MERIDIAN, MISSISSIPPI

PROJECT NUMBER:	22.006
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/2</u> 1 2 3	
SEAL	
SHEET TITLE:	

HUMAN SERVICES -MECHANICAL SCHEDULES

SHEET NUMBER

M6.2

MODULAR AIR HANDLING UNIT SCHEDULE	
------------------------------------	--

MO	JULAR AIR I	HANDLING	G UNIT S	CHED	OULE																				
	MANUFACTURER				S	SUPPL	Y FAN										DX	COOLING	COIL			FILTER			
TAG	AND MODEL NO.	TYPE	SUPPLY AIR	OUTDO	OOR AIR	ESP	RPM	ISOLA	TION	FAN	ELE	C (PER	FAN)		EDB	LDB		CAPACI	TY (MBH)	ROWS	TVPE			OP WT	REMARKS
			CFM	MAX	MIN	TSP		TYPE	DEFL	(QTY)	BHP	HP	V/Ø		EWB	LWB		TOTAL	SENS	FPI				(LBS.)	
AHU	TRANE	DIRECT-DRIVE	15700	15700	1150	2.0	1800	SPRING	2	2	14.4	7.5	208/3	450	78.0	54.9	0.63	537	306	4	PLTD	2"	12	3800	MARINE LED LIGHT PER SECTION - 120 15AMP CIRCUIT REQUIRED, 6" INTEGRAL BASE FRAME, PREMIUM EFF. I
1	CSAA035	PLENUM FAN	13700	13700	1150	3.4		SENING			14.4	EA	200/3	430	65.0	53.5	0.63	557	390	14		2	13	3000	GROUNDING, DOUBLE WALL W/HINGES & LATCHES, OA DAMPER, RA DAMPER, FAC MTD AIRFLOW MEASURING

ION G	ENERATORS	1						
TAG	MANUFACTURER & MODEL NO.	UNIT SERVED	SUPPLY CFM	DEVICES REQUIRED	DEVICE MOUNTING LOCATION	MIN ION OUTPUT PER DEVICE	POWER	REMARKS
IG-1	GLOBAL PLASMA GPS-IMOD	AHU-1	15700	SEE REMARKS	IN UNIT DOWNSTREAM OF FILTERS FULL LENGTH OF COIL	> 140 MILLION +/- IONS/CC PER INCH OF BAR	24 VAC TO 240 VAC	PROVIDE WITH: BUILT IN UNIVERSAL INPUT VOLTAGE TRANSFORMER, ON/OFF SWITCH AND LED POWER INDICATOR LIGHT, UL-2998 NO OZONE CERTIFIED, QUANTITY TO BE FIELD VERIFIED BASED ON COIL HEIGHT PER MANUFACTURE'S RECOMMENDATIONS
IG-2	GLOBAL PLASMA GPS-FC48-AC	AHU	1250-1800	1	IN UNIT DOWNSTREAM OF FILTERS	> 400 MILLION +/- IONS/CC	24 VAC TO 240 VAC	PROVIDE WITH: BUILT IN UNIVERSAL INPUT VOLTAGE TRANSFORMER, ON/OFF SWITCH AND LED POWER INDICATOR LIGHT, UL-2998 NO OZONE CERTIFIED

CON	COMPUTER ROOM AIR-CONDITIONING UNIT (INDOOR UNIT) SCHEDULE																					
	MANUFACTURER				SUPP	PLY FAN			D>	COOLING C	OIL	ELECTRIC	C REHEAT	HUMIDIFER		FILTERS		ELECTRI	CAL	SCOD	OP	
TAG	AND MODEL NO.	SERVES	TYPE	SUPPLY	OA	ESP		нр С	A ED	B CAPAC	CITY (KW)	NO.	CAPACITY		TYPE	DEPTH MERV	MCA	МОР	VOLT/Ø	SCOP -127	WT (LBS)	REMARKS
				CFM	CFM	TSP		''' TE	MP EN	B TOTAL	SENS	STAGES	(KW)	(LBS/HR)			WIO/ (INICI	VOEINO		(LD3)	
	TRANE TR-CFU-042-D2A-0-10	SERVER & COMPUTER	VERTICAL UPFLOW	8000	-0-	0.2	2	4.2 1	20 80 62	40.1	40.1	2	18	- 4-15	PLTD	2 8	102.5	110	208/3	-		INTEGRAL CONDENSATE PUMP, UNIT MOUNTED DISCONNECT, FLOORSTAND, UPFLOW PLENUM, SMOKE DETECTOR, BACnet MS/TP COMM CARD, ELECTRIC REHEAT, INFRARED HUMIDIFIER W/AUTOFLUSH

COMPUTER ROOM AIR-CONDITIONING UNIT (OUTDOOR UNIT) SCHEDULE												
TAG	MANUFACTURER AND MODEL NO	SERVES	NOM TONS	REFR TYPE	FLA			VOLT/Ø	OP WT (LBS)	REMARKS		
	TRANE TR-SCS-192-DEC	CRAC-1	-	410A	1@8.5 1@8.5	21.2	25.0	208/3	455	REMOTE CONDENSER, EC FAN MOTOR		

TAG	MANUFACTURER	INLET	DE	ESIGN CF	-M	TOTAL	NC				HEAT	ING COI	L			VOLTO	
TAG	AND MODEL NO	SIZE	COOL	MIN	HEAT	ΔP	NC.	ROWS	CFM	EAT	LAT	GPM	EWT	LWT	MBH	VOLT-Ø	F
(T-1.01)	TRANE VCCF05	5"	60	60	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
< <u>(</u> T-1.02)	TRANE VCWF08	8"	500	150	300	0.416	15	2	300	55	95	1.52	140	95	13.01	120-1	
(T-1.03)	TRANE VCWF08	8"	400	120	240	0.416	15	2	240	55	95	1.08	140	95	10.41	120-1	
√T-1.04	TRANE VCWF06	6"	240	70	140	0.416	15	2	140	55	95	0.05	140	99	6.69	120-1	
< <u>₹</u> -1.05	TRANE VCCF08	8"	380	110	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
< <u>₹-1.06</u>	TRANE VCCF06	6"	300	90	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
< <u>−1.07</u>	TRANE VCCF06	6"	200	60	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
(T-1.08)	TRANE VCCF10	10"	800	240	-	0.416	15	-	-	-	-	-	-	-	-	120-1	S C
																	s s
< <u>(</u> T-2.01)	TRANE VCCF06	6"	200	60	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
< <u>(</u> T-2.02)	TRANE VCCF06	6"	290	90	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
< <u>₹</u> 7-2.03	TRANE VCWF08	8"	400	120	240	0.416	15	2	240	55	95	1.08	140	95	10.41	120-1	
(T-2.04)	TRANE VCWF08	8"	630	180	380	0.416	15	2	380	55	95	2.40	140	95	16.48	120-1	
< <u>₹</u> -2.05	TRANE VCWF08	8"	580	170	350	0.416	15	2	350	55	95	2.02	140	95	-	120-1	S
(T-2.06)	TRANE VCWF08	8"	450	130	270	0.416	15	2	270	55	95	1.29	140	95	-	120-1	
(T-2.07)	TRANE VCCF10	10"	800	250	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
(T-2.08)	TRANE VCCF08	8"	400	120	-	0.416	15	-	-	-	I	-	-	-	-	120-1	
(T-2.09)	TRANE VCWF10	10"	1180	350	710	0.416	15	2	710	55	95	4.18	140	95	30.80	120-1	
(T-2.10)	TRANE VCCF06	6"	200	60	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
√T-2.1	TRANE VCWF10	10"	1210	370	730	0.416	15	2	730	55	95	4.55	140	95	31.67	120-1	
< <u>₹-2.12</u>	TRANE VCCF08	8"	400	120	-	0.416	15	-	-	-	-	-	-	-	-	120-1	
√T-2.13	TRANE VCWF08	8"	580	170	350	0.416	15	2	350	55	95	2.02	140	95	15.18	120-1	5
< <u>(</u> T-2.14)	TRANE VCWF08	8"	580	170	350	0.416	15	2	350	55	95	2.02	140	95	15.18	120-1	5
⟨T-2.15⟩	TRANE VCWF08	8"	400	120	240	0.416	15	2	240	55	95	1.08	140	95	10.41	120-1	S

SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER. BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR.

SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR. SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR.

SINGLE DUCT WITH HEATING COIL, FLOW RING, 24 VAC CONTROL TRANSFORMER, BOTTOM ACCESS DOOR.

MOTORIZED DAMPER SCHEDULE												
TAG	DAMPER MODEL	ACTU MODEL	ATOR VOLTAGE/PHASE	INTERLOCK	POWER WIRING	CONTROLS & INTERLOCK WIRING						
MD 1	RUSKIN CDRS-25	BELIMO	120/1	AHU-2	DIVISION 26	DIVISION 23 BAS						

SPLIT SYSTEM AIR HANDLING UNIT SCHEDULE

TAC	MANUFACTURER	NOMINAL		SUPPL	Y FAN				ELECT	RIC HE	AT	DX	COOLING COIL		FILTER		OPER	
TAG	& MODEL NO	TONS	SUPPLY CFM			MBH (TOTAL/SENSIBLE)	TYPE	DEPTH	MERV	(LBS)	REMARKS							
AHU 2	TRANE	5.0	1800	180	0.5	1/2	208 / 1	15	79	80	CBX26UH	80/67	60.8/45.6	THROW AWAY	1"	N.A.	300	PROVIDE WITH PROGRAMMABLE THERMOSTAT, FILTER SECTION, ION GENERATOR IG-2
AHU 3	TRANE	3.5	1250	130	0.5	1/3	208 / 1	10	53	60	CBX26UH	80/67	43.6/35.1	THROW AWAY	1"	N.A.	300	PROVIDE WITH PROGRAMMABLE THERMOSTAT, FILTER SECTION, ION GENERATOR IG-2

HEAT PUMP CONDENSING UNIT SCHEDULE

TAG MANUFACTURER SERVING NOM REFR ELECTRICAL	SEER	OPER WT	REMA	
	OLT/Ø	(LBS)		
CU TRANE AHU-2 5.0 410A 29.3 36.3 60 2	208 / 1 13.0	200		
CU TRANE AHU-3 3.5 410A 22.5 27.8 45 2	208 / 1 13.5	180		

MISCELLANEOUS HVAC POWER, CONTROL AND INTERLOCK WIRING CONNECTIONS

TAG	DESCRIPTION	POWER	CONTROL & INTERLOCK	ELECTRICAL	
TAG	DESCRIPTION	WIRING	WIRING	V/Ø	
М	MOTORIZED DAMPER	DIV 26 ELECTRICAL	DIV 23 BAS	120/1	
МСР	MASTER CONTROL PANEL	DIV 23 BAS	DIV 23 BAS	120/1	
wc	WIRELESS CONTROLLER	DIV 23 BAS	DIV 23 BAS	120/1	
LT	AHU LED LIGHTS	DIV 26 ELECTRICAL	DIV 23 HVAC	120/1	

FF. INVERTER DUTY MOTOR WITH SHAFT RING STATION, WALL MTD VFD'S, IG-1



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

REMARKS

TAMPERPROOF SUPERVISORY SWITCHES TO MONITOR VALVE STATUS. VERIFY/COORDINATE DEDICATED POWER OR SYSTEM POWER REQUIREMENTS. INTERLOCK WITH OCCUPANCY SENSOR IN ROOM IDU SERVED (SEE CONTROLS). 3-POSITION ACTUATOR.

ARKS

REMARKS

TAMPERPROOF SUPERVISORY SWITCHES TO MONITOR VALVE STATUS. VERIFY/COORDINATE DEDICATED POWER OR SYSTEM POWER REQUIREMENTS. DIVISION 26 ELECTRICAL SHALL PROVIDE NETWORK IT LAN DROP NEAR BUILDING CONTROLLER, PROVIDE LOW

VOLTAGE RELAY TO DE-ENERGIZE CONTROLS WITH OCCUPANCY BY BUILDING WEB BASED CONTROL (SEE WIRELESS CONTROL DIAGRAM)

PROVIDE 120VAC TO EXTERNAL JUNCTION BOX ON EACH AHU.

MISSISSIPPI GRADES LE COUNT AL UP MERIDIAN HVAC 4

PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	22
SEAL	

SHEET TITLE:

EMERGENCY SERVICES / EMA - HVAC SCHEDULES

SHEET NUMBER

M6.3

DUC.	TLESS SPLIT-	SYSTE	EM HEA		1P - II	NDO	OR U	NIT S	SCHEDULE
TAG	MANUFACTURER	TYPE	COOLING	HEATING	E	LECTRIC	4L	OPER WT	REMARKS
TAG	& MODEL NO		(MBH)	(MBH)	VOLT/Ø	FLA	MOCP	(LBS)	REMARKS
	TRANE/MITSUBISHI NTXCKS15A112AA	4-WAY CASSETTE	14.1	19.1	208/1	.32	18	30	WALL MOUNTED REMOTE CON
	TRANE/MITSUBISHI NTXCKS15A112AA	4-WAY CASSETTE	14.1	19.1	208/1	.32	18	30	WALL MOUNTED REMOTE CON
	TRANE/MITSUBISHI NTXWPH06B112AA	WALL MTD	9.0	14.0	208/1	.65	15	30	WALL MOUNTED REMOTE CON
	TRANE/MITSUBISHI NTXWPH06B112AA	WALL MTD	9.0	14.0	208/1	.65	15	30	WALL MOUNTED REMOTE CON
DSS 5	TRANE/MITSUBISHI NTXWPH06B112AA	WALL MTD	9.0	14.0	208/1	.65	15	30	WALL MOUNTED REMOTE CON
DSS 6	TRANE/MITSUBISHI NTXWST36B112AA	WALL MTD	33.2	36.0	208/1	.76	20	50	WALL MOUNTED REMOTE CON
DSS 7	TRANE/MITSUBISHI NTXWST36B112AA	WALL MTD	33.2	36.0	208/1	.76	20	50	WALL MOUNTED REMOTE CON

DUCI	LESS SPLIT-	SYS	STEM	1 HE	AT PUM	1P - OU	TDC	OR	UNIT	SC⊦	IEDU	JLE	
	MANUFACTURER	NOM	REFR	OAT	CAPACI	ГҮ (MBH)	E	ELECTR	CAL			OPER	
TAG	& MODEL NO	TONS	TYPE	COOL HEAT	COOLING	HEATING	MCA	моср	VOLT/Ø	SEER	HSPF	WT (LBS)	REM
CU	TRANE/MITSUBISHI	1.25	410A	95.0	14.1	19.1	10.0	18	208/1	19.8	11.2	100	INVE
	NTXSK15A112AA	1.20	410A	47.0	14.1	13.1	10.0	10	200/1	13.0	11.2	100	
CU	TRANE/MITSUBISHI	1.25	410A	95.0	14.1	19.1	10.0	18	208/1	19.8	11.2	100	INVE
2	NTXSK15A112AA	1.20	410/	47.0	17.1	10.1	10.0	10	200/1	10.0	11.2	100	IIIV L
CU	TRANE/MITSUBISHI	.75	410A	95.0	9.0	14.0	10.0	15	208/1	33.1	12.5	100	INVE
3	NTXSPB06B112AA	.15	410/	47.0	0.0	14.0	10.0	10	200/1	00.1	12.0	100	
CU	TRANE/MITSUBISHI	.75	410A	95.0	9.0	14.0	10.0	15	208/1	33.1	12.5	100	INVE
4	NTXSPB06B112AA	.75	410/	47.0	5.0	14.0	10.0	10	200/1	00.1	12.0	100	
CU	TRANE/MITSUBISHI	.75	410A	95.0	9.0	14.0	10.0	15	208/1	33.1	12.5	100	INVE
5	NTXSPB06B112AA	.75	410/	47.0	5.0	14.0	10.0	10	200/1	00.1	12.0	100	
	TRANE/MITSUBISHI	3.0	410A	95.0	33.2	36.0	19.0	20	208/1	16.2	10.0	125	INVE
6	NTXSST36B112AA	3.0	410/	47.0	00.2	50.0	10.0	20	200/1	10.2	10.0	120	
CU	TRANE/MITSUBISHI	3.0	410A	95.0	33.2	36.0	19.0	20	208/1	16.2	10.0	125	INVE
7	NTXSST36B112AA	3.0	410/4	47.0	00.2	50.0	13.0	20	200/1	10.2	10.0	125	

POW	OWER VENTILATOR SCHEDULE												
TAG	MANUFACTURER AND MODEL NO.	TYPE	CFM	ESP	RPM	SOUND (dBA/SONES)			AL V/Ø	ON/OFF	INTERLOCK	OP WT (LBS)	REMARKS
EF 1	COOK 150SQN10D	CENTRIFUGAL INLINE CABINET FAN	1520	0.5	1071	59/9.0	.26	1/3	115/1	(2)MOTION DETECTOR	MD-1 & MD-2	100	DIRECT DRIVE, TWO2) MOTION DETECTOR, PREWIRED DISCONNECT, PREWIRED FAN SPEED CONTROLLER, BACKDRAFT DAMPER, RUBBER-IN-SHEAR ISOLATORS
EF 2	COOK 90SQN17DEC	CENTRIFUGAL INLINE CABINET FAN	300	0.35	1354	52/5.9		1/6	115/1	MOTION DETECTOR	NONE	100	ECM MOTOR, PREWIRED DISCONNECT, BACKDRAFT DAMPER, RUBBER-IN-SHEAR ISOLATORS
EF 3	COOK 90SQN17DEC	CENTRIFUGAL INLINE CABINET FAN	300	0.35	1354	52/5.9		1/6	115/1	MOTION DETECTOR	NONE	100	EC MOTOR, PREWIRED DISCONNECT, BACKDRAFT DAMPER, RUBBER-IN-SHEAR ISOLATORS
EF 4	COOK GCVF-100	CEILING MOUNTED	75	0.25	808	1.3		.26A	115/1	MOTION DETECTOR	NONE	-	EC MOTOR, PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAMPER, ISOLATOR KIT, WHITE ALUMINUM GRILLE
EF 5	COOK GCVF-100	CEILING MOUNTED	75	0.25	808	1.3		.26A	115/1	MOTION DETECTOR	NONE	-	EC MOTOR, PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAMPER, ISOLATOR KIT, WHITE ALUMINUM GRILLE
EF 6	COOK GCVF-100	CEILING MOUNTED	75	0.25	808	1.3		.26A	115/1	MOTION DETECTOR	NONE	-	EC MOTOR, PRE-WIRED DISCONNECT, PRE-WIRED FAN SPEED CONTROLLER, BACKDRAFT DAMPER, ISOLATOR KIT, WHITE ALUMINUM GRILLE

DEH	DEHUMIDIFIER UNIT SCHEDULE							
TAG	MANUFACTURER	CFM	PINTS/ 24	ELECTRICAL		REMARKS		
170	AND MODEL NO.	CI M	HRS	VOLT/Ø	AMPS			
DH 1	HONEYWELL TRUEDRY DR65	100	65	115/1	5.2	HARD DRAIN CONNECTION, 10' CORD WITH PLUG, MERV 11 FIL MOUNTED) WITH LCD DISPLAY, PINTS/24 HRS IS BASED ON 80 ° CONDENSATE PUMP		
DH 2	HONEYWELL TRUEDRY DR65	100	65	115/1	5.2	HARD DRAIN CONNECTION, 10' CORD WITH PLUG, MERV 11 FIL MOUNTED) WITH LCD DISPLAY, PINTS/24 HRS IS BASED ON 80 ° CONDENSATE PUMP		
DH 3	HONEYWELL TRUEDRY DR65	100	65	115/1	5.2	HARD DRAIN CONNECTION, 10' CORD WITH PLUG, MERV 11 FIL MOUNTED) WITH LCD DISPLAY, PINTS/24 HRS IS BASED ON 80 CONDENSATE PUMP		
DH 4	HONEYWELL TRUEDRY DR65	100	65	115/1	5.2	HARD DRAIN CONNECTION, 10' CORD WITH PLUG, MERV 11 FIL MOUNTED) WITH LCD DISPLAY, PINTS/24 HRS IS BASED ON 80 ° CONDENSATE PUMP		
DH 5	HONEYWELL TRUEDRY DR65	100	65	115/1	5.2	HARD DRAIN CONNECTION, 10' CORD WITH PLUG, MERV 11 FIL MOUNTED) WITH LCD DISPLAY, PINTS/24 HRS IS BASED ON 80 ° CONDENSATE PUMP		

ONTROLLER, INDOOR UNIT RECEIVES POWER FROM OUTDOOR UNIT, CONDENSATE PUMP
ONTROLLER, INDOOR UNIT RECEIVES POWER FROM OUTDOOR UNIT, CONDENSATE PUMP
ONTROLLER, INDOOR UNIT RECEIVES POWER FROM OUTDOOR UNIT, CONDENSATE PUMP
ONTROLLER, INDOOR UNIT RECEIVES POWER FROM OUTDOOR UNIT, CONDENSATE PUMP
ONTROLLER, INDOOR UNIT RECEIVES POWER FROM OUTDOOR UNIT, CONDENSATE PUMP
ONTROLLER, INDOOR UNIT RECEIVES POWER FROM OUTDOOR UNIT, CONDENSATE PUMP
ONTROLLER, INDOOR UNIT RECEIVES POWER FROM OUTDOOR UNIT, CONDENSATE PUMP

EMARKS

VERTER COMPRESSOR, LOW AMBIENT KIT, WALL MOUNT BRACKET

MOTORIZED DAMPER SCHEDULE

TAG	DAMPER	ACTU	ATOR		POWER WIRING	CONTROLS & INTERLOCK WIRING	REMARKS			
170	MODEL	MODEL	VOLTAGE/PHASE	INTEREOOR			REMARKO			
	RUSKIN CDRS-25	BELIMO	120/1	EF-1	DIVISION 26	DIVISION 23 BAS	TAMPERPRO SYSTEM PO 3-POSITION			
MD 2	RUSKIN CDRS-25	BELIMO	120/1	EF-1	DIVISION 26	DIVISION 23 BAS	TAMPERPRO SYSTEM PO 3-POSITION			
	TAG MD 1 MD	TAG DAMPER MODEL MD RUSKIN CDRS-25 MD RUSKIN	TAG DAMPER MODEL ACTU MODEL MD RUSKIN CDRS-25 BELIMO MD RUSKIN BELIMO	TAG DAMPER MODEL ACTUATOR MD RUSKIN CDRS-25 MODEL VOLTAGE/PHASE MD RUSKIN BELIMO 120/1	TAGDAMPER MODELACTUATOR MODELINTERLOCKMD 1RUSKIN CDRS-25BELIMO120/1EF-1MD 1RUSKIN CDRS-25BELIMO120/1EF-1	TAG DAMPER MODEL ACTUATOR INTERLOCK POWER WIRING MD 1 RUSKIN CDRS-25 BELIMO 120/1 EF-1 DIVISION 26 MD RUSKIN BELIMO 120/1 EF-1 DIVISION 26	TAG DAMPER MODEL ACTUATOR INTERLOCK POWER WIRING CONTROLS & INTERLOCK WIRING MD RUSKIN 1 BELIMO 120/1 EF-1 DIVISION 26 DIVISION 23 BAS MD RUSKIN BELIMO 120/1 EF-1 DIVISION 26 DIVISION 23 BAS			

FILTER, DIGITAL HUMIDITY CONTROLLER (WALL 80 °F / 60% RH ENTERING AIR CONDITIONS,

FILTER, DIGITAL HUMIDITY CONTROLLER (WALL 80 °F / 60% RH ENTERING AIR CONDITIONS,

FILTER, DIGITAL HUMIDITY CONTROLLER (WALL 80 °F / 60% RH ENTERING AIR CONDITIONS,

FILTER, DIGITAL HUMIDITY CONTROLLER (WALL 80 °F / 60% RH ENTERING AIR CONDITIONS,

FILTER, DIGITAL HUMIDITY CONTROLLER (WALL 80 °F / 60% RH ENTERING AIR CONDITIONS,

AIR DISTRIBUTION DEVICE SCHEDULE

T/	AG	TYPE	MANUFACTURER & MODEL NO.	NECK SIZE	FACE SIZE	REMARKS
,	A	CEILING MOUNTED SUPPLY AIR DEVICE	TITUS OMNI	SEE PLANS/ SCHEDULE BELOW	SEE PLANS/ SCHEDULE BELOW	24"x24" OR 12"x12" FACE SIZE AS INDICATED FRAME MOUNT (TITUS TRM). NECK SIZE TO
	В	CEILING MOUNTED EXHAUST/RETURN	TITUS 50F	SEE PLANS/ SCHEDULE BELOW	SEE PLANS/ SCHEDULE BELOW	12"x12" OR 24"x12" FACE SIZE AS INDICATED WITH SCREW HOLES. NECK SIZE TO BE AS I
NOT	ES:					
1	CEII	ING DIFFUSERS ARE 4				

CEILING DIFFUSERS ARE 4-WAY UNLESS OTHERWISE NOTED BY SHADING ON PLANS.
 REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPE AND CONSTRUCTION DETAILS.

3. AIR DEVICE FRAME AND STYLE SHALL MATCH CEILING TYPE. COORDINATE WITH ARCHITECTURAL REFLECTED CEILING PLAN.

4. REFER TO ARCHITECT FOR FINISHES AND COLOR OF DEVICES.

5. FACE SIZE TO BE NECK SIZE PLUS 2".

AIR QUANTITY (CFM)	CEILING MOUNTED NECK SIZE	SIDE
0-100	6"Ø	
101-200	8"Ø	
201-350	10"Ø	
351-600	12"Ø	

						ENGINEE FRESOURCE O S50 EDGEWOOD TERR JACKSON, MS 39206 PHONE: (601) 362-355 FAX: (601) 366-6418 CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313	SROUP AACE DRIVE
						PROJECT:	
						HVAC UPGRADES LAUDERDALE COUNTY	MERIDIAN, MISSISSIPPI
	TEM POWER REQUIREM DSITION ACTUATOR. PERPROOF SUPERVISO TEM POWER REQUIREM DSITION ACTUATOR.	ENTS. INTERLOCK WITH RY SWITCHES TO MONIT ENTS. INTERLOCK WITH	OCCUPANCY SENSOR TOR VALVE STATUS. VE OCCUPANCY SENSOR	ERIFY/COORDINATE DEDI IN ROOM IDU SERVED (S ERIFY/COORDINATE DEDI IN ROOM IDU SERVED (S	SEE CONTROLS).	PROJECT NUMBER: DATE: DRAWN BY: CHECKED BY: REV: 0_IFC 10/4/202 1 2 3 SEAL	КАН СЕМ 22
S	SIZE TO BE AS INDICATE DICATED ON PLANS. PRC BE AS INDICATED ON P	OVIDE ALL SURFACE MOU D ON PLANS OR CONNECT OVIDE ALL SURFACE MOU LANS OR CONNECTION S ONNECTION SCHEDULE	CTION SCHEDULE BELC			SHEET TITLE:	
	SIDEWALL MOUNTED NECK SIZE	EXHAUST AIR GRILLE NECK SIZE	BRANCH [AGRI-CENTE MECHANIC	
			ROUND	ALTERNATE RECTANGULAR DUCT		SCHEDULES - ALT. #1	
	8x4"	8x8"	6"Ø	8x4"			
	10x6" 12x8"	8x8" 10x10"	8"Ø 10"Ø	10x6" 		SHEET NUMBER	
_							-

CONSTRUCTION DOCUMENTS

12x12"

14x10"

M6.4

ints List	Table (Column
Point	Descrip	tion.
	•	r in poin
		alog ou
		log inpu
		gital or b
		tal or bi
Device	e descri	ption.
		becificat
		definitic
Trend	Loggin	α.
		issioning
		ssioning
4.2.		uous: W
		d after s
4.3.	Trend I	
-		Where
		(COV)
		value
	4.3.2.	Where

Calibration

of each

General:

- the system.

- followed:
- without it.
- required for ASC hardware points.

CONTROL POINTS	S	EQ
mn Definitions:	2.	Zone
point list schedule after each type refers to tag on schematics). g output input or binger cutout	А. В.	This such Setp a.

l or binary output or binary input

fication Section 230913 EMCS Basic Materials and Devices for initions and specifications.

oning: Where listed, point is to be trended at the basis listed for oning and performance verification purposes. is: Where listed, point is to be trended at the basis listed continuously,

ter system acceptance, for the purpose of future diagnostics. here range of engineering units is listed, trend on a change of value

COV) basis (in other words record time stamp and value when point alue changes by engineering unit listed). Vhere time interval is listed, trend on a time basis (in other words

record time stamp and value at interval listed). All points related to a specific piece of equipment shall be trended at the same initiation time of day so data can be compared in text format.

5.1. F = factory calibration only is required (no field calibration) 5.2. HH = field calibrate with handheld device. Test/calibration equipment shall be

at least twice as accurate as respective field device (for example if field device is $\pm 0.5\%$ accurate, test equipment shall be $\pm 0.25\%$ accurate over same range). Note that points lists herein are for each system of like kind. Refer to Drawings for quantity

SEQUENCES OF OPERATION - GENERAL

Contractor shall review sequences prior to programming and suggest modifications where required to achieve the design intent. Contractor may also suggest modifications to improve performance and stability or to simplify or reorganize logic in a manner that provides equal or better performance. Proposed changes in sequences shall be included as a part of Submittal Package 2.

Include costs for program modifications if required to provide proper performance of

Unless otherwise indicated in SOOs, control loops shall be enabled and disabled based on the status of the system being controlled to prevent wind-up. Loops shall be initiated with the output set to a neutral (deadband) condition, e.g. valves and dampers close, VFDs at minimum speed, etc.

When SOOs use outdoor air temperature present value and there are multiple outdoor air sensors, the physically closet sensor reading shall be used.

The term "proven" (i.e. "proven on" / "proven off") shall mean that the equipment's DI status point matches the state set by the equipment's DO command point. The term "PID loop" or "control loop" is used generically for all control loops and shall not be interpreted as requiring proportional plus integral plus derivative gains on all loops. Unless specifically indicated otherwise, the following guidelines shall be

a. Use proportional only (P-only) loops for limiting loops (such as zone CO2 limiting loops, etc.) to ensure there is no integral windup. b. Do not use the derivative term on any loops unless field tuning is not possible

G. All setpoints, timers, deadbands, PID gains, etc. listed in sequences shall be capable of being adjusted by the operator (with full administrative access) without having to access programming whether indicated as adjustable in sequences or not. Software (virtual) points shall be used for these setpoints. Fixed scalar numbers shall not be imbedded in programs unless the value will never need to be adjusted. Values for all points, including real (hardware) points used in control sequences shall be capable of being overridden by the user (e.g. for testing and commissioning). If hardware design prevents this for hardware points, they shall be equated to a software point and the software point shall be used in all sequences. Exception: Not

SEQUENCES OF OPERATION - GENERAL CONT'D

section applies to all single zone systems and sub-zones of air handling systems, as VAV boxes, fan-powered boxes, etc.

Each zone shall have separate unoccupied and occupied setpoints, and separate heating and cooling setpoints. As a default:

Zone Type	Оссі	upied	Unoccupied		
Zone Type	Heat	Cool	Heat	Cool	
Exterior	70°F	74°F	60°F	90°F	
Interior	70°F	73°F	60°F	90°F	
Circulation	69°F	76°F	60°F	90°F	
Mech/Elec Rooms	60°F	85°F	60°F	85°F	
Network/IT	65°F	75°F	65°F	75°F	

b. The software shall prevent:

- The heating setpoint from exceeding the cooling setpoint minus 1°F (in other words the minimum deadband shall be 1°F). • The unoccupied heating setpoint from exceeding the occupied heating
- setpoint; and
- The unoccupied cooling setpoint from being less than the occupied cooling setpoint
- c. Where the zone has a local occupant adjustable setpoint adjustment knob/button:
- The adjustment shall be capable of being limited in software. • As a default, occupied cooling setpoint shall be limited between 72°F and 80°F. •• As a default, occupied heating setpoint shall be limited between 65°F and 72°F.
- The adjustment shall move both the existing heating and cooling setpoints upwards or downwards by the same amount unless the limit has been reached.
- The adjustment shall only be active in Occupied mode.
- d. The operative setpoint shall be determined by the Zone Group's mode:
- The setpoints shall be the occupied setpoint during Occupied mode, Warm-up mode, and Cool-down mode. The setpoints shall be the unoccupied setpoints during Unoccupied mode, Setback mode, and Setup mode.
- e. Hierarchy of Setpoint Adjustments: The following adjustment restrictions shall prevail in order from highest to lowest priority:
- Setpoint overlap restriction specified herein. • Local setpoint adjustment.
- Scheduled setpoints based on Zone Group mode.

Local override: When thermostat override buttons are depressed, the request for Occupied Mode operation shall be sent up to the Zone Group control for 60 minutes. (This will cause all zones in the Zone Group to operate in Occupied Mode to ensure that the system has adequate load to operate stably.)

D. Control Loops:

- a. Two separate control loops shall operate to maintain space temperature at setpoint, the Cooling Loop and the Heating Loop. Both loops shall be continuously active.
- b. The Cooling Loop shall maintain the space temperature at the active cooling setpoint. The output of the loop shall be a virtual point ranging from 0% (no cooling) to 100% (full cooling).
- c. The Heating Loop shall maintain the space temperature at the active heating setpoint. The output of the loop shall be a virtual point ranging from 0% (no heating) to 100% (full heating). d. Loops shall use proportional + integral logic or fuzzy logic. Proportional-only
- control is not acceptable, although the integral gain shall be small relative to the proportional gain. P and I gains shall be adjustable from the Operator Workstation. e. See other sections for how the outputs from these loops are used.

E. Zone Modes:

- a. Heating Mode: when the output of the space heating control loop is greater than
- b. Cooling Mode: when the output of the space cooling control loop is greater than zero and the output of the heating loop is equal to zero.

c. Deadband Mode: when not in either the Heating or Cooling Mode.

Alarms:

- a. Zone temperature alarms: If the zone is 3°F above cooling or below heating setpoints for 10 minutes, generate Level 3 alarm.
- if the zone is 5°F above cooling or below heating setpoints for 10 minutes, generate Level 2 alarm.
- Suppress zone temperature alarms as follows: • After zone setpoint is changed for a period of 10 minutes per degree of difference between the zone temperature at the time of the change and the new setpoint. This suppression period applies any time that the zone
- setpoint is changed. • While Zone Group is in Warm-up or Cool-down Modes. • For zones with an Importance multiplier (see Trim & Respond sequences

above) of zero.

b. For zones with CO2 sensors: • If the CO2 concentration is less than 300 ppm, or the zone is in unoccupied mode for more than 2 hours and zone CO2 concentration exceeds 600 ppm, generate a Level 4 alarm, indicating sensor may be out of calibration. • If the CO2 concentration exceeds setpoint plus 10% for more than 10

minutes generate a Level 3 alarm.

3. Zone Groups (aka Isolation Areas):


A. Each system shall be broken into separate Zone Groups composed of a collection of one or more zones served by the air handling system.

- Each Zone Group shall have separate occupancy schedules and operating modes from other Zone Groups served by the air handling system. All zones in the Zone Group shall be in the same operating mode.
- Individual Zone Groups shall be setup per the Owner's written requirements. Contractor shall confirm Zone Groups from Owner (in writing) prior to initial
- programming. Provide testing/commissioning software switches to override all zones served by the Zone Group. Provide a single software switch for each of the zone override switches listed under terminal box control above. When the Zone Group override switch value is changed, the terminal box zone override switch value for each zone in the Zone Group shall change to the same value. This only occurs when the switch changes value; the switch at each zone shall be capable of being changed to a different value from the Zone Group switch. These software switches are for commissioning and need not be shown on graphics.

SEQUENCES OF OPERATION - GENERAL CONT'D

E. Zone Group Operating Modes: Each Zone Group shall have the following modes: a. Occupied Mode: A Zone Group is in the occupied mode when any of the following is true: • The time of day is between the Zone Group's scheduled occupied start and

- stop times. • Manual override from zone temperature sensor.
- b. Warm-up mode. Warm-up start time shall be determined based on the zone in the Zone Group whose space temperature is furthest below its occupied heating temperature setpoint, the outside air temperature (using global outdoor air temperature sensor, not any associated with AHUs), and a building mass/capacity factor. This factor shall be manually adjusted or self-tuned by the program based on internal trending so that all zones in the Zone Group are brought up to their occupied setpoint by the scheduled occupied start hour. The tuning period mode shall be turned on or off by a software switch (to allow tuning to be stopped after the system has been trained). Warm-up mode shall start no earlier than 3 hours before the scheduled occupied start hour and shall end at the scheduled occupied start hour.
- Cool-down mode. Cool-down shall be determined based on the zone in the Zone Group whose space temperature is furthest above its occupied cooling temperature setpoint, the outside air temperature (using global outdoor air temperature sensor, not any associated with AHUs), and a building mass/capacity factor. This factor shall be manually adjusted or self-tuned by the program based on internal trending so that all zones in the Zone Group are brought down to their occupied setpoint by the scheduled occupied start hour. The tuning period mode shall be turned on or off by a software switch (to allow tuning to be stopped after the system has been trained). Cool-down mode shall start no earlier than 3 hours before the scheduled occupied start hour and shall
- end at the scheduled occupied start hour. d. Setback mode. During other than normal mode, and warm-up mode, if any 2 (adjustable; set to all zones if there are fewer in Zone Group) zone(s) in the Zone Group falls 2°F below its active unoccupied setback setpoint, until all spaces in
- the Zone Group are above their active setback setpoints. e. Setup mode. During other than normal mode, warm-up mode, and setback mode, if any 2 (adjustable; set to all zones if there are fewer in Zone Group) zone(s) in the Zone Group rises 2°F above its active unoccupied setup setpoint until all spaces in the Zone Group are below their active setup setpoints. e.1.1. Unoccupied Mode: When the Zone Group is not in any other mode.
- 4. Air Handling Unit, Fan Coil Unit, Blower Coil Unit, Split-System Unit System Modes:
- AHU, FCU, BCU, and/or Split-System modes are the same as the mode of the Zone
- Groups served by the system. When Zone Groups served by an air handling system are in different modes, the following hierarchy applies (highest one sets AHU mode): a. Occupied mode.
- . Cool-down mode
- Setup mode.
- d. Warm-up mode. e. Setback mode.
- f. Unoccupied mode.
- Miscellaneous Alarms:
- Points in Hand (Operator Override) via Workstation command (including name of operator who made the command) or via supervised HOA switch at output: Level 4. Equipment alarm (for equipment with alarm contacts such as VFDs): Level 2. C. Failure or disconnection of a sensor as indicated by signal widely out of range: Level
- D. Panel or LAN failure: Level 2.
- E. Loss of communication with any device via Gateway (e.g. VFD) for more than 30 seconds: Level 2 (alarm shall indicate which specific device is not responding).



NETWORK CONNECTION BETWEEN CONTROLLER AND DEVICE

ЦЩ



EQUIPMENT

 \mathbb{A}

SD

0000

 \square

ENABLE

RUN 🗆

SPEED 🗆

NETWORK

VFD

HAND 🗆

OFF AUTO 🗆

M/S

SENSORS

Δ

E

HT-X | TS-X

TS-X

М

M2

DPS-X

DPT-X

FM-X

TS-X

HT-X

CO2-X

CTH_O

NII

WLD-X

RC

OUTSIDE/OUTDOOR AIR

HARDWIRED DIGITAL OUTPUT (DO) OR DIGITAL INPUT (DI)

HARDWIRED ANALOG OUTPUT (AO) OR ANALOG INPUT (AI)

CONTROLS LEGEND

2-WAY VALVE

3-WAY VALVE

SMOKE DETECTOR

FAN - PROPELLER

FAN - CENTRIFUGAL HOUSED

FAN - PLUG / PLENUM

FURNACE

FILTER

AIR FLOW MEASURING STATION

COIL

OPPOSED BLADE DAMPER

PARALLEL BLADE DAMPER

VARIABLE SPEED DRIVE

MOTOR STARTER (MOTOR CONTROLLER)

STATIC PRESSURE TIP

SENSOR WELL

TEMPERATURE SENSOR & SENSOR WELL

HUMIDITY TRANSMITTER (HT) OR TEMPERATURE SENSOR (TS) - DUCT MTD. (SINGLE POINT)

AVERAGING TEMPERATURE SENSOR

MODULATING ACTUATOR

2-POSITION ACTUATOR DIFFERENTIAL PRESSURE SWITCH

DIFFERENTIAL PRESSURE TRANSMITTER

FLOW METER

TEMPERATURE SENSOR - WALL MTD.

HUMIDITY TRANSMITTER - WALL MTD.

CARBON DIOXIDE SENSOR - WALL MTD.

OCCUPANCY SENSOR

CURRENT SWITCH

CURRENT TRANSFORMER RELAY N.C. / N.O.

WATER LEAK DETECTOR VARIABLE REFRIGERANT FLOW SYSTEM INDOOR UNIT REMOTE CONTROLLER

CONSTRUCTION DOCUMENTS

RESOURCE GROUP 350 EDGEWOOD TERRACE DRIVE JACKSON, MS 39206 PHONE: (601) 362-3552 FAX: (601) 366-6418 CONSULTANTS: **ELECTRICAL ENGINEER** SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313


5

ENGINEERING

PROJECT:

SISSIP MIS RIDIA C K ∢ш Ш

Σ




SHEET TITLE:

CONTROL SCHEMATICS

M7.1

SHEET NUMBER



POINT MAPPED FROM VRF SYSTEM

			Trend L	ogging	Calibra-	
Description	Туре	Device	Comm- issioning	Contin- uous	tion	
Outdoor Unit Status	DI	Through network	COV	COV	-	
Branch Controller Status	DI	Through network	COV	COV	_	
Indoor Unit Mode	DI	Through network	COV	COV	-	
Alarms	DI	Through network	COV	COV	-	
Indoor Unit Enable	DO	Through network	COV	COV	-	
Zone Temperature	Al	Through network	15 min	60 min	-	
Zone Temperature Setpoint Adjustment	AO	Through network	COV	COV	_	
Zone Temperature Limits	AO	Through network	-	-	-	
Time-of-Day Scheduling	AO	Through network	-	-	-	
Fan Speed Setting	AO	Through network	COV	-	-	
Air Flow Direction	AO	Through network	_	_	_	
Permit/Prohibit Function	AO	Through network	COV	_	_	



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

MISSISSIP

MERIDIAN

.NNO

ADES

C

UP

HVAC (LAUDERD

General: Once enabled via the Energy Management and Control System (EMCS), the Variable Refrigerant Flow (VRF) system shall operate subject to its own internal

See Sequence of Operation - General for setpoints, loops, control modes, alarms, etc.


- BAS shall enable/disable, schedule system modes, monitor system parameters, and change setpoints for the VRF system via the BACnet gateway.
- Division 23 HVAC Contractor shall be responsible for initial VRF system setup, programming, point naming, schedules, setpoints, etc (system configuration). Division 23 HVAC Contractor and VRF system vendor shall provide technical support to the Section 230900 EMCS (Division 23C) Contractor in mapping across EMCS points.
- Zone Temperature Control: Zone temperature shall be controlled via each indoor unit's remote controller within the temperature limits specified.


5.1. Maintenance interval alarm when unit has operated for more than 1500 hours: Level 5. Reset interval counter when alarm is acknowledged.

PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	
SEAL MD E. M PROFE UGILEER 20102 0/4/2023 0/5 MISS	
SHEET TITLE:	
HUMAN SER CONTROL SCH	-


SHEET NUMBER

M7.2





OUTDOOR AIR UNIT CONTROL SCHEMATIC





NOTES 🗰

CONTROL DEVICE FACTORY PROVIDED, FIELD INSTALLED BY DIV 23C EMCS CONTRACTOR.

2. CONTROL DEVICE FACTORY PROVIDED, FACTORY INSTALLED.

3. FOR UNITS WITH MULTIPLE SUPPLY FANS, PROVIDE A VFD FOR EACH FAN. SEE DOAS EQUIPMENT SCHEDULE FOR SUPPLY FAN QUANTITY.

			Trend L	ogging	Calibra-ti	<u>General</u> : Constant Air Volume (CAV) Outdoor Air Unit (OAU) with DX cooling, hot gas reheat (HGRH), modulating gas heat, and supply fan(s)	
Description	Туре	Device	Comm- issioning	Contin-uo us	on	<u>OA System Modes</u> : OAU system mode shall be in the occupied mode 24/7. EMCS graphic shall include a switch to manually swith the OAU from occupied to unoccupied mode.	
Supply Fan Start/Stop	DO	Through network	cov	cov	_	Occupied mode Unoccupied mode	
Cooling Stage 1	DO	Through network	COV	COV	_		
Cooling Stage 2	DO	Through network	COV	COV	-	Supply Fan Control:	
Cooling Stage 3	DO	Through network	COV	COV	_	1. Supply Fan Start/Stop	
Cooling Stage 4	DO	Through network	COV	COV	_	1.1. RTU supply fan(s) shall run when system is in Occupied Mode.	
Unit Mode (Cooling, Heating, Dehumidification)	DO	Through network	COV	COV	_	 Unit shall be hard-wire interlocked through smoke detector. Supply Fan Speed Control 	
Compressor lead-lag	DO	Through network	COV	COV	_	2.1. Supply fan speed is controlled to maintain the OA flow rate at the design CFM when the fan is proven on.	
						Supply Air Temperature Control	
Unit mode (Occupied, Unoccupied,						1. Control loop is enabled when the supply air fan is proven on and disabled and output set to zero	
Cool-down, Warm-up, Setup, Setback)	DO	Through network	COV	COV	_	 otherwise. 2. The leaving evaporator coil temperature shall be controlled to setpoint (52°F adjustable) using a PID loop whose output is mapped to sequence the cooling stages and variable speed compressor. 	
Supply fan status	DI	Through network	COV	COV	_	3. The supply air temperature shall be controlled to setpoint (72°F adjustable) using a PID loop whose output is mapped to sequence the hot gas reheat coil and natural gas heat exchanger.	
OA damper status	DI	Through network	COV	COV	_		
Unit alarm contact	DI	Through network	COV	COV		Safeties and Interlocks:	
Supply fan speed	AO	Through network	1 min	60 min		1. Supply fan shall be hardwire interlocked through the unit smoke detector to shut down the unit	
Variable speed compressor output	AO	Through network	1 min	60 min		upon smoke detection. EMCS Alarms: Provide the following EMCS alarms:	
Heat output	AO	Through network	1 min	60 min		1 Maintananaa interval alarm when unit has operated for more than 1500 hours: Loval 5. Reset	
OA damper position	AO	Through network	1 min	60 min		 Maintenance interval alarm when unit has operated for more than 1500 hours: Level 5. Reset interval counter when alarm is acknowledged. Fan alarm is indicated by the status being different from the command for a period of 60 	
Discharge air temperature setpoint	AO	Through network	1 min	60 min		seconds. 2.1. Commanded on, status off: Level 2 2.2. Commanded off, status on: Level 4	
OA damper minimum position setpoint	AO	Through network	1 min	60 min		 Filter pressure drop exceeds alarm limit: Level 5. The alarm limit shall vary with fan speed as follows: 	
OA minimum flow setpoint	AO	Through network	1 min	60 min		$DPx = DP100(x)^{1.4}$	
Humidity high-limit	AO	Through network	1 min	60 min		Where DP100 is the high limit pressure drop at design cfm (determine limit from filter manufacturer) and DPx is the high limit at speed signal x (expressed as a fraction of full signal). For instance, the	
Cooling capacity	AI	Through network	1 min	60 min		setpoint at 50% of full speed would be (0.5)^1.4 or 38% of the design high limit pressure drop.	
Heating capacity	AI	Through network	1 min	60 min		4. High supply air temperature (more than 5 °F above setpoint) when control loop is active for	
Reheat capacity	AI	Through network	1 min	60 min		longer than 15 minutes: Level 3.If the outside air temperature is above the supply air temperature setpoint and the economizer is	
Discharge air temperature	AI	Through network	1 min	60 min		enabled and the mixed air temperature is more than 2 °F different from the outside air temperature for more than 30 minutes continuously; OR if the outdoor air temperature is more	
Reheat capacity	AI	Through network	1 min	60 min		than 5 °F below the supply air temperature setpoint and the chilled water valve is open: Level 4 indicating economizer damper control problems.	
Filter runtime hours	AI	Through network	1 min	60 min		6. Low static pressure (more than 0.25 inches below setpoint) when fan control loop is active for longer than 5 minutes: Level 3.	
OA temperature	AI	Through network	1 min	60 min		 High building pressure (more than 0.1") for 5 minutes. Level 3. Low building pressure (less than 0.0") for 5 minutes. Level 4. 	
OA flow rate	AI	Through network	1 min	60 min		9. Outdoor airflow less than setpoint by 10% for 10 minutes when loop is active: Level 3.	
OA humidity	AI	Through network	1 min	60 min		Testing/Commissioning Overrides: Provide software points that interlock to a chilled water and hot	
Space humidity	AI	Through network	1 min	60 min		water plant level point to:	
						Force all stages of cooling on. Force all stages of cooling off. Force gas heat to 100%. Force gas heat off.	

POINTS MAPPED FROM OAU BACNET CARD

OAU SEQUENCE OF OPERATION

EF W/MOTION DETECTOR SEQUENCE OF OPERATION

General: Constant volume exhaust fan(s).

- 1. See Sequence of Operation General for setpoints, loops, control modes, alarms, etc.
- 2. Exhaust fans shall operate if restroom is occupied as indicated by the motion detector. Fan shall run until the time delay duration has been exceeded. Time delay setting shall be initially set for 20 minutes.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

S

Ш О

1

C C C

MISSISSIPPI -NUO \mathbf{O} Ш DAL U D MERIDIAN, I HVAC (AUDERD


PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 IFC 10/4/202 1 2 3	
SEAL	

SHEET TITLE:

HUMAN SERVICES -CONTROL SCHEMATICS

SHEET NUMBER

M7.3



VAV AHU CONTROL SCHEMATIC - EMERGENCY SERVICES/EMA (AHU-1) M7.4 NO SCALE

1

	AHU HARDWIRED POINTS L						AHU SEQUENCE OF OPERATION				
	Description	Туре	Device	Trend L Comm- issioning	ogging Contin- uous	Calibra- tion	<u>General</u> : Variable Air Volume (VAV) Air Handling Unit (AHU) with pre-he water coil, supply fan(s). The sequence of operation is based on ASHRA 36-2021. Refer to the guideline for additional information and commental				
	Supply Fan Start/Stop Supply fan high static	DO	Connect to VFD "Run" Dry contact to 120V or	COV	COV	_	AHU System Modes: AHU system modes are the same as the mode of t				
	alarm reset	DO	24V control circuit	COV	COV	-	served by the system. When Zone Groups served by an air handling sys modes, the following hierarchy applies (highest one sets AHU mode):				
	DX cooling stage 1	DO	Dry contact to 120V or 24V control circuit	cov	COV	-	1. Occupied mode				
	DX cooling stage 2	DO	Dry contact to 120V or 24V control circuit	cov	COV	-	 Cool-down mode Setup mode 				
	DX cooling stage 3	DO	Dry contact to 120V or 24V control circuit	cov	COV	_	4. Warm-up mode 5. Setback mode 6. Unaccupied mode				
	DX cooling stage 4	DO	Dry contact to 120V or 24V control circuit	cov	cov	-	6. Unoccupied mode				
	Water leak detector	DI	WLD-1	COV	COV	-	Supply Fan Control:				
	Outdoor air damper Return air damper	AO AO	Modulating actuator Modulating actuator	1 min 1 min	15 min 15 min	-	1. Supply Fan Start/Stop				
	Supply fan speed	AO	Connect to VFD Speed	1 min	15 min 15 min	_	 AHU supply fan(s) shall run when system is in any mode othe Mode. 				
	Mixed air temperature	AI	TS-1B, across filter bank	1 min	15 min	_	1.2. Fan VFD's shall be hard-wire interlocked through smoke detectors pressure safety relay mounted in the control panel in each AHU co				
	Filter pressure drop	AI	DPT-2A, 0 to 1 inch	_	60 min	-	relay energizes when high-limit DP switches sense pressure above (adjustable) at the fan discharge or smoke detector auxiliary contac				
	Return air temperature	AI	TS-1A	1 min	15 min	-	locking out the fans until they are reset by the reset DO point or a p				
	Supply air temperature	AI	TS-1A	1 min	15 min	-	panel face. A pilot light on the panel face indicates static pressure effect.				
	Duct static pressure	AI	DPT-2A, 0 to 2 inches	1 min	15 min	-	 Totalize current airflow rate from VAV boxes and display on AHU g duct. 				
	OA flow OA temperature	Al Al	AFMS-1 AFMS-1	1 min 1 min	15 min 15 min	-	2. Static Pressure Setpoint Reset				
	· · ·						2.1. Static pressure setpoint: Setpoint shall be reset using Trim &				
				Trend L			(see Trim & Respond description herein) with the following pa				
	Description	Туре	Device	Comm-	Contin-	Calibra- tion	Variable Value Device Supply Fan				
				issioning	uous		SP0 0.5 inches				
	Fault reset On/off status	DO DI	Through network Through network	COV COV	COV COV	-	SPmin 0.1 inches				
	Fault (Critical Alarm)	DI	Through network	cov	cov		SPmax Max_DSP Per TAB Agency				
	Minor Alarm	DI	Through network	COV	COV	-	Td 10 minutes				
	Fault Text	DI	Through network (convert code to plain	cov	COV	_	T 2 minutes				
			Ènglish text) Through network				Zone Static R Pressure Reset				
	Alarm Text	DI	(convert code to plain English text)	cov	COV	-	Requests				
	Keypad in hand/auto	DI	Through network	COV	COV	_	SPtrim -0.05 inches SPres +0.06 inches				
	Minimum frequency setpoint	AO	Through network	±5%	±5%	-	SPres-max +0.13 inches				
	Maximum frequency setpoint	AO	Through network	±5%	±5%	_	3. Static Pressure Control				
	Acceleration rate	AO	Through network	±5%	±5%	_	3.1. Supply fan speed is controlled to maintain DSP at set point w proven ON. Where the zone groups served by the system are				
	Deceleration rate	AO	Through network	±5%	±5%	-	multiple sets of gains that are used in the control loop as a fu				
	Actual frequency AC output voltage	Al Al	Through network Through network	1 min ±10%	15 min ±10%		indicator (such as supply-fan airflow rate, the area of the zone occupied, etc.).				
	Current	AI	Through network	15 min	60 min	_	Supply Air Temperature Control:				
	VFD temperature	AI	Through network	60 min	60 min	-	1. Control loop is enabled when the supply air fan is proven ON and di				
OUCT STATIC PROBE	Power, kW Energy, MWh	Al Al	Through network Through network	1 min 15 min	15 min 60 min	-	set to zero otherwise. 2. Supply Air Temperature Setpoint: 55 °F.				
OCATE 2/3 DOWN DOCT	DC Bus Voltage	AI	Through network	±10%	±10%	_	 Supply air temperature shall be controlled to setpoint using a PID lo mapped to stage the DX cooling stages to maintain the supply air te 				
							setpoint.				
							Minimum Outdoor Airflow Set Points:				
							1. Outdoor Airflow Set Point for ASHRAE Standard 62.1 Ventilation.				
							1.1. Refer to Guideline 36 Section 5.2.1.3.5 for zone outdoor air re				
							 Refer to Guideline 36 Section 3.1.4.2.1 for set points DesVou Outdoor air absolute minimum and design minimum set point continuously based on the mode of the zones being served. 				
							1.3.1. Calculate the uncorrected outdoor air rate Vou for all zor groups that are in occupied mode, but note that Vou sha				
)							the design uncorrected outdoor air rate DesVou. Vou = MIN(DesVou, $\Sigma V_{bz} - A + \Sigma V_{bz} - P$)				
							 Vps is the sum of the zone primary airflow rates Vpz as meas boxes for all zones in all zone groups that are in occupied mode. For each zone in occupied mode, calculate the zone primary 				
,							Zpz: Zpz = Voz/Vpz				
							1.6. Calculate the maximum zone outdoor air fraction Zp:				
							Zp = max(Zpz)				
							1.7. Calculate the current system ventilation efficiency Ev:				
							Ev = 1 + (Vou/Vps) - Zp				
							1.8. Calculate the effective minimum outdoor air set point MinOAs uncorrected outdoor intake divided by the system ventilation of larger than the design total outdoor air rate DesVot:				
							MinOAsp = MIN(Vou/Ev , DesVot)				
							Minimum Outdoor Air Control:				
							1. Minimum Outdoor Air Control Loop.				
							1.1. Minimum outdoor air control loop is enabled when the supply and the AHU is in Occupied Mode and disabled and output se				
							otherwise. 1.2. The outdoor airflow rate shall be maintained at the minimum setpoint MinOAsp by a reverse-acting control loop whose out the outdoor air damper minimum position MinOA-P and return maximum position MaxRA-P as indicated in Figure 1.				

AHU SEQUENCE OF OPERATION

e-heat coil, chilled IRAE Guideline ntary.

of the Zone Group system are in different BAS Alarms:

other than Unoccupied ors and high discharge

I control panel. The ove 3.0 inches ntacts are energized, a push button on the

ure safety lockout is in

U graphic at discharge

n & Respond Logic g parameters.



nt when the fan is are small, provide a function of a load one groups that are

d disabled and output

D loop whose output is r temperature

r requirement Voz. /ou and DesVot. pints are recalculated

zones in all zone shall be no larger than

easured by VAV mode. ary outdoor air fraction

OAsp as the on efficiency, but no

ply fan is proven on it set to zero

ım outdoor air output is mapped to turn air damper

AHU SEQUENCE OF OPERATION CON'T

Safeties and Interlocks:

Supply fan shall be hardwire interlocked through the unit smoke detector(s) and high static pressure switch to shut down the unit upon smoke detection.


- Maintenance interval alarm when unit has operated for more than 1500 hours: Level 4. Reset interval counter when alarm is acknowledged. . Fan alarm is indicated by the status being different from the command for a period of 60 seconds.
- 2.1. Commanded ON, status off: Level 22.2. Commanded OFF, status on: Level 4
- Filter pressure drop exceeds alarm limit: Level 5. The alarm limit shall vary with fan speed as follows:


 $DPx = DP100(x)^{1.4}$

Where DP100 is the high limit pressure drop at design cfm (determine limit from filter manufacturer) and DPx is the high limit at speed signal x (expressed as a fraction of full signal). For instance, the setpoint at 50% of full speed would be $(0.5)^{1.4}$ or 38% of the design high limit pressure drop.

. High building pressure (more than 0.1") for 10 minutes. Level 3. 5. Low building pressure (less than 0.0") for 10 minutes. Level 4.

Testing/Commissioning Overrides: Provide software points that interlock to a chilled water and hot water plant level point to:







CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:


MISSISSIPPI **RADES** COUNT UPGR/ DALE 0 MERIDIAN HVAC (AUDERD

PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/2</u> 1 2 3 SEAL SEAL SEAL SEAL SEAL SEAL SEAL SEAL SEAL SEAL SEAL SEAL SEAL SEAL	
SHEET TITLE:	

EMERGENCY SERVICES / EMA -CONTROL SCHEMATICS

SHEET NUMBER

M7.4



HW SYSTEM HARDWIRED POINTS LIST

			Trend L	ogging	Calibra-	G
Description	Туре	Device	Comm- issioning	Contin- uous	tion	1.
Boiler B-1 enable	DO	Connect to boiler enable contact	COV	COV	-	
HWP-1 start/stop	DO	Dry Contact to 120V starter control circuit	COV	COV	-	
PHWP-1 start/stop	DO	Dry Contact to 120V starter control circuit (coordinate with existing pump/boiler)	COV	COV	_	2.
B-1 setpoint	AO	Connect to boiler setpoint input	1 min	15 min	_	
HWP-1 status	DI	CS-1	COV	COV	-	
PHWP-1 status	DI	CS-1	COV	COV	-	
Boiler B-1 Alarm	DI	Connect to boiler alarm contact	COV	COV	-	3.
HWS temperature (leaving boiler)	AI	TS-2B	1 min	±2°F	-	4.
HWR temperature (entering boiler)	AI	TS-2B	1 min	±2°F	_	, т.
HWS temperature (to system)	AI	TS-2B	1 min	±2°F	_	
HWR temperature (from system)	AI	TS-2B	1 min	±2°F	-	
						1



> HWS

HW SYSTEM SEQUENCE OF OPERATION

General: HW system with existing atmospheric boiler, primary pump, and secondary pump.

Lead boiler and pump.

1.1. The HW system shall be enabled if there are more than 3 (adjustable) Boiler Plant Requests from zones for more than 10 minutes (adjustable). 1.2. The HW system shall be disabled if it has run at least 10 minutes and there are no Boiler Plant Requests from zones for more than 10 minutes (adjustable).

Boiler and pumps.

- 2.1. When the lead system is enabled, first start the boiler primary pump and simultaneously start the HW secondary pump, then after 30 seconds, enable the boiler. When the HW system is disabled, first disable the boiler, then after 3 minutes turn off the pumps. 2.2. Pumps speed shall be constant speed.
- Boiler Supply Water Temperature:
- 3.1. Leaving Boiler Supply Water temperature setpoint shall be 180 °F.

Variable

SP0

SPmin

SPmax

Td

Т

SPtrim

SPres

SPres-max

4.1. Hot water supply temperature setpoint shall be reset using Trim & Respond

Device HWS temperature

logic (see Sequence of Operation - General) based on hot water pump status

Value

SPmax

150°F

180°F

10 minutes

5 minutes

2

-2°F

+3°F +7°F

Hot Water Supply Temperature Reset:

with the following parameters:



ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

5. Boiler Emergency Shutdown Switch.

5.2. Boiler shall require a manual reset.

- 5.1. Boiler shall be disabled when he Boiler Emergency Shutdown Switch (ESS) is enabled.
- 6. Alarms.
- 6.1. Maintenance interval alarm when pump has operated for more than 1500 hours:
- Level 5. Reset interval counter when alarm is acknowledged. 6.2. Maintenance interval alarm when boiler has operated for more than 2000 hours: Level 5. Reset interval counter when alarm is acknowledged.
- 6.3. Boiler alarm: Level 2. 6.4. Low boiler leaving hot water temperature (more than 15°F below setpoint) for more than 15 minutes when boiler has been enabled for longer than 15
- minutes: Level 3. 6.5. Low boiler return hot water temperature (less than 140°F) for more than 15 minutes when boiler has been enabled for longer than 15 minutes: Level 2. 6.6. Pump alarm is indicated by the status input being different from the output command after a period of 15 seconds after a change in output status.
 - 6.6.1. Commanded on, status off: Level 2.
 - 6.6.2. Commanded off, status on: Level 4.

C L L

PROJECT:

MISSISSIPP RADES COUN⁻ UP MERIDIAN HVAC (AUDERD


PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/2</u> 1 2 3	
SEAL	

SHEET TITLE:

EMERGENCY SERVICES / EMA -CONTROL SCHEMATICS

SHEET NUMBER

M7.5



SPLIT-SYSTEM HP SEQUE

General: Constant volume split-system heat pump.

System Modes: System modes are the same as the system. When Zone Groups served by an air handlir following hierarchy applies (highest one sets AHU r

- Occupied mode 2. Cool-down mode
- 3. Setup mode
- 4. Warm-up mode 5. Setback mode
- 6. Unoccupied mode

Supply Fan Control: Unit controller shall control the as follows:

- Start/Stop: Unit controller shall command the enabled. Unit controller shall command the sup Proof: Unit controller shall prove fan operation. to accumulate runtime. Upon failure of the sup alarm.
- Supply fan shall run at the speed corresponding speed shall be determined in conjunction with the speed shall be determined in conjunction with th Agency.

Heat Pump Control:

1. The EMCS shall control the operation of the he 2. EMCS shall control cycling of the reversing val operation.

Zone Temperature Control (Cooling):

Cooling control loop shall be enabled when the and output set to zero when fan is off. 2. Zone temperature shall be controlled to setpoin enabling the compressor as required to mainta

Zone Temperature Control (Heating):

- Heating control loop shall be enabled when the
- and output set to zero when fan is off.
- Zone temperature shall be controlled to setpoi and enabling the compressor as required to m

Safeties and Interlocks:

Supply fan shall be hardwire interlocked throug down the unit upon smoke detection.

EMCS Alarms: Provide the following EMCS alarm

- Maintenance interval alarm when unit has oper Reset interval counter when alarm is acknowle Fan alarm is indicated by the status being diffe 60 seconds.
- 2.1. Commanded on, status off: Level 2 2.2. Commanded off, status on: Level 4

POINT MAPPED FROM TS-2A CONTROLLER

			Trend L	Calibra-	
Description	Туре	Device	Comm- issioning	e e e e e e e e e e e e e e e e e e e	
Unit Status	DI	TS-4, Through network	COV	COV	_
System mode	DI	TS-4, Through network	COV	COV	_
Fan mode	DI	TS-4, Through network	COV	COV	-
Alarms	DI	TS-4, Through network	COV	COV	_
Occupancy/override	DI	TS-4, Through network	COV	COV	_
Aux.heat status	DI	TS-4, Through network	COV	COV	-
Fan status	DI	TS-4, Through network	COV	COV	-
Cooling status	DI	TS-4, Through network	COV	COV	_
Heating status	DI	TS-4, Through network	COV	COV	_
Reversing valve	DI	TS-4, Through network	COV	COV	_
Unit enable	DO	TS-4, Through network	COV	COV	_
Zone temperature	AI	TS-4, Through network	5 min	60 min	_
Zone humidity	AI	TS-4, Through network	5 min	60 min	_
Zone IAQ	AI	TS-4, Through network	5 min	60 min	-
Zone Temperature Setpoint Adjustment	AO	TS-4, Through network	COV	COV	_
Zone Temperature Limits	AO	TS-4, Through network	COV	COV	_
Time-of-Day Scheduling	AO	TS-4, Through network	-	-	-
Fan Speed Setting	AO	TS-4, Through network	COV	COV	_
Permit/Prohibit Function	AO	TS-4, Through network	COV	COV	_

ENCE OF OPERATION	CRAC L	JNIT	SEQUENCE OF	OPER	ATION			
p. the mode of the Zone Group served by the ndling system are in different modes, the J mode):	 <u>General</u>: Computer Room Air Conditioning (CRAC) Unit. EMCS shall monitor CRAC unit's nardwired and network points for diagnostic purposes. All alarms shall be displayed at the DWS. CRAC unit shall be controlled by it's internal controller and shall run subject to it's own internal safeties. Alarms: 2.1. Generate a Level 5 maintenance alarm when unit has operated for more than 5000 hours. Reset interval counter when alarm is acknowledged. 							
the starting and stopping of the supply fan		CRA	C UNIT POINTS	S LIST				
				Trend L	ogging			
e supply fan on when the system is supply fan off when the system is disabled.	Description	Туре	Device	Comm- issioning	Contin- uous	Calibra- tion		
on. EMCSS shall use the status indication supply fan, unit controller shall enunciate an	CRAC Leak	DI	Connect to CRAC leak detection contact	COV	COV	_		
ding to the design supply air flow rate. Fan th the Testing, Adjusting, and Balancing	CRAC Alarm	DI	Connect to CRAC Alarm contact	COV	COV	_		
	CRAC Supply Air Temp	AI	Connect to CRAC SAT contact	COV	COV	-		
	POINTS MAP	PED	FROM CRAC U	INIT BA	CNET (CARD		
heat pump as described herein below. valve as required, based on mode of	Description	Туре	Device	Trend Logging		Calibra-		
	Description			Comm- issioning	Contin- uous	tion		
	Unit Enable	DO	Through network	COV	COV	_		
the supply fan is proven on, and disabled	Local Alarm Present	DI	Through network	COV	COV	_		
	Dehumidification	DI	Through network	COV	COV	_		
point by energizing the reversing valve and ntain the zone temperature setpoint.	Humidification	DI	Through network	COV	COV	_		
	Reheat	DI	Through network (convert code to plain English text)	COV	COV	_		
the supply fan is proven on, and disabled point by de-energizing the reversing valve maintain the zone temperature setpoint.	Unit Status	DI	Through network (convert code to plain English text)	COV	COV	_		
	Water Detection	DI	Through network	COV	COV	_		
	Dirty Filter	DI	Through network	COV	COV	_		
ough the unit smoke detector(s) to shut	Cooling Stages On	AO	Through network	COV	COV	_		
	Heating Stages On	AO	Through network	COV	COV	_		
	CHW Valve Position	AO	Through network	1 min	60 min	_		
ms:	HW Valve Posiiton	AO	Through network	1 min	60 min	_		
perated for more than 1500 hours: Level 5.	CHW Runtime	A1	Through network	1 min	60 min	_		
vledged. ifferent from the command for a period of	HW Runtime	AI	Through network	1 min	60 min	_		
merent nom the command for a period of	Temperature Setpoint	AO	Through network	COV	COV	_		
	Humidity Setpoint	AO	Through network	COV	COV	_		
	Discharge Air Temperature	AI	Through network	1 min	60 min	_		
	Return Air Temperture	AI	Through network	1 min	60 min	-		
	Relative Humidty	AI	Through network	1 min	60 min			



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

MISSISSIPPI **RADES** COUNT UPGR/ DALE C MERIDIAN HVAC (AUDERD


PROJECT	
NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/2</u> 1 2 3	022
SEAL DE CONSTRUCTION DE CONSTRUCTION	

SHEET TITLE:

EMERGENCY SERVICES / EMA -CONTROL SCHEMATICS

SHEET NUMBER

M7.6



VAV REHEAT CONTROL SCHEMATIC - EMERGENCY SERVICES/EMA M7.7 NO SCALE

VAV TERMINAL UNIT SEQUENCE OF OPERATION

General: Variable Air Volume (VAV) Terminal Unit with hot water reheat. The VAV terminal unit sequence of operation is based on ASHRAE Guideline 36 -2021 VAV Terminal Unit with Reheat. Refer to Guideline 36 for additional information and commentary.

See Sequence of Operation - General for setpoints, loops, control modes, alarms, etc.

See Sequence of Operation - General for calculation of zone minimum outdoor airflow.

Design airflow rates shall be as scheduled on plans:

- 1. Zone maximum cooling airflow set point (Vcool-max).
- 2. Zone minimum airflow set point (Vmin). 3. Zone maximum heating airflow set point (Vheat-max).

4. Maximum Discharge Air Temperature (DAT) rise above heating set point Max ΔT .

Active maximum and minimum set points shall vary depending on the mode of the zone group the zone is a part of.

Setpoint	Occupied	Cool-down	Setup	Warm-up	Setback	Unoccupied
Cooling maximum	Vcool-max	Vcool-max	Vcool-max	0	0	0
Cooling minimum	Vmin*	0	0	0	0	0
Minimum	Vmin*	0	0	0	0	0
Heating minimum	Max(Vheat- min, Vmin*)	Vheat-max	0	Vheat-max	Vheat-max	0
Heating maximum	Max(Vheat- max, Vmin*)	Vheat-max	0	Vcool-max	Vcool-max	0

Control logic is depicted schematically in Figure 1 and described in the following subsections. Relative levels of various set points are depicted for occupied mode operation.

When the zone state is cooling, the cooling-loop output shall be mapped to the airflow set point from the cooling minimum to the cooling maximum airflow set points. Heating coil is disabled unless the DAT is below 50°F.

1. If supply air temperature from the air handler is greater than room temperature, cooling supply airflow set point shall be no higher than the minimum.

When the zone state is deadband, the active airflow set point shall be the minimum airflow set point. Heating coil is disabled unless the DAT is below 50°F.

When the zone state is heating, the heating loop shall maintain space temperature at the heating set point as follows:

- From 0% to 50%, the heating-loop output shall reset the discharge temperature set point from the current AHU SAT set point to a maximum of Max∆T above space temperature set point. The airflow set point shall be the heating minimum.
- From 51% to 100%, if the DAT is greater than room temperature plus 5°F, the heating-loop output shall reset the airflow set point from the heating minimum airflow
- set point to the heating maximum airflow set point. The heating coil shall be modulated to maintain the discharge temperature at set point.
- 3.1. When the airflow set point is pulse-width modulated (time-averaged ventilation), the heating coil and PID loop shall be disabled, with output set to 0 during closed periods.

Alarms:

1. Low Airflow:

- 1.1. If the measured airflow is less than 70% of set point for 5 minutes, while set
- point is greater than zero, generate a Level 3 alarm. 1.2. If the measured airflow is less than 50% of setpoint for 5 minutes, while set
- point is greater than zero, generate a Level 2 alarm.
- 1.3. If a zone has a Importance-Multiplier of 0 for its static pressure reset trim and

2. Low-Discharge Air Temperature:

- 2.1. If boiler plant is proven ON and the DAT is 15°F less than set point for 10
- minutes, generate a Level 3 alarm.
- 2.2. If boiler plant is proven ON and the DAT is 30°F less than set point for 10 minutes, generate a Level 2 alarm.
- 2.3. If a zone has a Importance-Multiplier of 0 for its hot water reset trim and
- 3. Airflow Sensor Calibration:
- 3.1. If the fan serving the zone has been OFF for 10 minutes, and airflow sensor reading is above 10% of the cooling maximum airflow set point, generate a Level 3 alarm.
- 4. Leaking Damper:
- 4.1. If the damper position is 0%, and airflow sensor reading is above 10% of the cooling maximum airflow set point for 10 minutes while the fan serving the zone is proven ON, generate a Level 4 alarm.
- 5. Leaking Valve:

level point to:

5.1. If the valve position is 0% for 15 minutes, DAT is above AHU SAT by 5°F, and


Testing/Commissioning Overrides: Provide software switches that interlock to a system

- 1. Force zone airflow set point to zero.
- 2. Force zone airflow set point to Vcool-max.
- 3. Force zone airflow set point to Vmin.
- 4. Force zone airflow set point to Vheat-max. 5. Force damper full closed/open.
- 6. Force heating to OFF/closed.
- 7. Reset request-hours accumulator point to zero (provide one point for each reset type listed below).


System Requests:

. Cooling SAT Reset Requests:

- 1.1. If the zone temperature exceeds the zone's cooling set point by 5°F for 2
- minutes and after suppression period due to set point change, send 3 requests.
- minutes and after suppression period due to set point change, send 2 requests.
- 1.3. Else if the cooling loop is greater than 95%, send 1 request until the loop is less
- than 85%. 1.4. Else if the cooling loop is less than 95%, send 0 requests.
- 2. Static Pressure Reset Requests:
- 2.1. If the measured airflow is less than 50% of set point while set point is greater than zero and the damper position is greater than 95% for 1 minute, send 3 requests.
- 2.2. Else if the measured airflow is less than 70% of set point while set point is greater than zero and the damper position is greater than 95% for 1 minute, send 2 requests.
- 2.3. Else if the damper position is greater than 95%, send 1 request until the damper position is less than 85%.
- 2.4. Else if the damper position is less than 95%, send 0 requests.



(Directly controlling heating off the zone temperature control loop is not acceptable).



respond control loop, low airflow alarms shall be suppressed for that zone.

respond control loop, low DAT alarms shall be suppressed for that zone.

the fan serving the zone is proven ON, generate a Level 4 alarm.

1.2. Else if the zone temperature exceeds the zone's cooling set point by 3°F for 2

VAV SEQUENCE OF OPERATION CON'T 3. Hot Water Reset Requests:

3.1. If the DAT is 30°F less than set point for 5 minutes, send 3 requests.

- 3.2. Else if the DAT is 15°F less than set point for 5 minutes, send 2 requests. 3.3. Else if the HW valve position is greater than 95%, send 1 request until the HW
- valve position is less than 85%. 3.4. Else if the HW valve position is less than 95%, send 0 requests.

4. Boiler Plant Requests:

4.1. If the HW valve position is greater than 95%, send 1 request until the HW valve position is less than 10%. 4.2. Else if the HW valve position is less than 95%, send 0 requests.




FIGURE 1

VAV HARDWIRED POINTS LIST

			Trend L	Calibra-	
Description	Туре	Device	Comm- issioning	Contin- uous	tion
Zone Override	DI	TS-3C	COV	COV	-
Zone Occupancy	DI	Occupancy Sensor	COV	COV	-
VAV Box Damper Position	AO	Modulating actuator	1 min	15 min	_
HW Valve Signal	AO	2-way valve	1 min	15 min	_
Supply Airflow		DPT-4 connected to box manufacturer supplied flow cross	1 min	15 min	_
Supply Air Temperature	AI	TS-1A	1 min	15 min	_
Zone Temperature Setpoint Adjustment	AI	TS-3C	15 min	15 min	_
Zone Temperature	AI	TS-3C	1 min	15 min	_
Zone Humidity	AI	HT-2	1 min	15 min	_
Zone CO2	AI	CO2-1	5 min	15 min	-

PROJECT:

5

JACKSON, MS 39206 PHONE: (601) 362-3552 FAX: (601) 366-6418

CONSULTANTS:

ELECTRICAL ENGINEER

4523 OFFICE PARK DR.

JACKSON, MS 39206

T: (601) 982-3313

SCHULTZ & WYNNE, P.A.

ENGINEERING

RESOURCE GROUP

350 EDGEWOOD TERRACE DRIVE

SISSIPI $\overline{\Box}$ MIS 7 \frown HVAC I MERIDIA

PROJECT NUMBER:	22.006
DATE:	10/4/2022
DRAWN BY:	KAH
CHECKED BY:	CEM
REV: 0 <u>IFC 10/4/20</u> 1 2 3	
SEAL	

SHEET TITLE:

EMERGENCY SERVICES / EMA -CONTROL SCHEMATICS


SHEET NUMBER

M7.7


DSS CONTROL WIRING SPECIFIED


OUTDOOR UNIT

DUCTLESS SPLIT-SYSTEM CONTROL SCHEMATIC - AGRI-CENTER ADD ALT. #1 1 M7.8 NO SCALE



2 EXHAUST FAN CONTROL SCHEMATIC - AGRI-CENTER M7.8 NO SCALE





DSS S	SEQUENCE	OF OPE	ERATION

<u>General</u>: Ductless split-systems.

- 1. See Sequence of Operation General for setpoints, loops, control modes, alarms, etc.
- 2. Ductless split-systems (DSS) shall be controlled by their wired remote controller.
- 2.1. Cooling setpoint = 78°F.2.2. Heating setpoint = 68°F.

3. EMCS to monitor space temperature.

Setpoints shall be setup per the following:

MISCELLANEOUS POINTS LIST					
			Trend Logging		Calibra
Description	Туре	Device	Comm- issioning	Contin- uous	Calibra- tion
Ductless Split-System Zone Temperature	AI	TS-3A	1 min	15 min	-
EF W/MOTION DET. SEQUENCE OF OPERATION					

<u>General</u>: Constant volume exhaust fan(s), controlled by motion detector(s).

1. See Sequence of Operation - General for setpoints, loops, control modes, alarms, etc.

 Exhaust fans shall operate if restroom is occupied as indicated by the motion detector(s). Fan shall run until the time delay duration has been exceeded. Time delay setting shall be initially set for 20 minutes.



CONSULTANTS: ELECTRICAL ENGINEER SCHULTZ & WYNNE, P.A. 4523 OFFICE PARK DR. JACKSON, MS 39206 T: (601) 982-3313

PROJECT:

MERIDIAN, MISSISSIPPI **RADES** COUNT UPGR/ DALE 0 HVAC (LAUDERD

PROJECT		
NUMBER:	22.006	
DATE:	10/4/2022	
DRAWN BY:	KAH	
CHECKED BY:	CEM	
REV: 0 <u>IFC 10/4/2022</u> 1 2 3		
SEAL UNIT DE AN DE AN DE AN DE AN DE AN PROPERTY		

SHEET TITLE:

AGRI-CENTER -CONTROL SCHEMATICS

SHEET NUMBER

M7.8